Z:\JOBS\T\TREEHOUSE\BLADE SIGN

SPECIFICATIONS QTY. 1 D/F
1" DEEP FABRICATED ALUMINUM BLADE SIGN CABINET PTD. WHITE.
GRAPHICS & COPY TO BE DIGITAL PRINT VINYL.
BRACKET MTD. TO BRICK FACE OF BUILDING.
MOUNTING TO BE THROUGH MASONRY JOINTS, NOT BRICKS.

SUPPORT FASTENERS TO GO INTO MORTAR JOINTS.
BASE PLATES TO BE DRILLED IN THE FIELD

WHITE
PMS P 17-6 C
PMS 285C

Project:

Location:

Date: 7.1.20 J

Revision:
A 8.13.20 B
B 8.18.20 J
C 8.31.20 J
D 10.14.20 J
E 11.23.20 J
F 12.2.20 J
G 12.8.20 J
H

Approval:

Name:

Sales: RM

USS Logo ☐ Yes ☐ No

Notes:

UNIVERSAL SIGN SYSTEMS
5001 Falcon View SE, Grand Rapids MI 49512
www.universalsignsystems.com
Ph 616.554.9999 Fx 616.554.9922