



Quote: 1384 / Date: 6/9/2025

Customer

Midwest Power Systems
2401 Hickory Oak Lane
Milford, MI
48380, US
+12487705127

Prepared By:
Matt Shaeffer
(248) 770-5124
midwestpower@hotmail.com

Ann Arbor Wastewater Treatment Plant
49 S. Dixboro Road
Ann Arbor, Michigan
48105

Adam Smith
7348450335
asmith@a2gov.org

Project: **Ann Arbor Screw Pumps Change Order Request**

Scope of Work

The original screw pump flight proposal had listed the supplier as providing wedge style anchors. Unfortunately, the supplier ended up sending epoxy chemical adhesive to be used with threaded rod.

The new epoxy adhesive will take more man hours for installation. To install the new anchors each hole must be blown out with air, wire brushed, and then blown out again. Then, you have to wait for the epoxy to set up before tightening the hardware.

Total anchors: 62

Extra time per anchor: 15 min.

Total extra time for installation: 15.5 hours

Three men per day that includes tools and service crane truck: \$3,900

Total extra days needed: 2

Notes

1. Chemical anchors supplied by others.



Quote: 1384 / Date: 6/9/2025

Summary

Subtotal	\$7,800.00
----------	------------

\$7,800.00

Accepted By

Date

.....

.....