

**CITY OF ANN ARBOR  
UTILITIES DEPARTMENT CHANGE ORDER  
CHANGE ORDER NO. 2**

Date: October 24, 2022 Encumbrance Order No. \_\_\_\_\_ Change Order No. 2

File No. 22001 Contractor Weiss Construction Co., LLC


Contract Name Barton Pump Station Valve Improvements – ITB 4703 DWSRF No. 7569-01


No.	Description of Change	Quantity	Unit	Unit Price	Addition (Deduction)
1	Additional Work Items (1)	NA	NA	NA	\$ 42,944.00
Sub-total from page 2				\$	42,944.00
Net Addition or (Deduction) this Change Order No. 2				\$	42,944.00
Contract amount ± previous Change Order No. 1				\$	4,749,081.50
<b>NEW TOTAL CONTRACT AMOUNT</b>				\$	<b>4,792,025.50</b>


Completion: 730 calendar days from NTP (4/1/22) = 3/31/2024 (no change)


Recommended by:  Date 10/24/2022  
Ken Jewison, PE, Stantec Project Manager

**The Contractor agrees to the changes and prices outlined above.**

Accepted by:  Date 10/25/2022  
Chris Klaft, Weiss Construction Co., LLC

Approved by:  10/28/2022 Date \_\_\_\_\_  
**BRIAN STEGLITZ, PUBLIC SERVICES AREA ADMINISTRATOR** Administrator

Approved by:  11/07/2022 Date \_\_\_\_\_  
**MILTON DOHONEY JR., CITY ADMINISTRATOR**

Reviewed by:  11/04/2022 Date \_\_\_\_\_  
**ATLEEN KAUR, CITY ATTORNEY**

**CHANGE ORDER NO. 2**

Project: Barton Pump Station Valve Improvements  
ITB Number: 4703  
Page 2 of 3

<b>Description</b>	<b>Unit Price</b>	<b>Quantity</b>	<b>Value Change</b>	<b>Contract Time Extension (Consecutive Calendar Days)</b>
1) Deleted scope to install 42-inch intake piping (PCO 960002)	1	LS	\$(61,134.00)	
2) 36-inch Linestop/Removal of Sluice Gate (PCO 960003)	1	LS	\$ 38,029.00	
3) Custom Steel Fitting (PCO 960006)	1	LS	\$ 66,049.00	
<b>Final Total Value of Changes</b>			<b>\$ 42,944.00</b>	

## CHANGE ORDER NO. 2

Project: Barton Pump Station Valve Improvements  
ITB Number: 4703  
Page 3 of 3

### Change Item Explanation

1. Deleted scope to install 42-inch intake piping (PCO 960002): Through a value engineering phase, there was scope identified for removal from the project. A portion of the proposed 42-inch intake piping originally designed to accommodate future improvements was deleted and a credit issued for labor, equipment, and materials associated with this work. The credit for this scope removal is \$61,134.00.
2. 36-inch Linestop/Removal of Sluice Gate (PCO 960003): Upon inspection to verify conditions and take field measurements of the sluice gate at Barton Hydroelectric Facility, it was determined that as-found conditions were not as anticipated, and this work could not be performed without significant additional effort and cost. Installation of a linestop on the 36-inch raw water suction line was identified as the most feasible alternate means of isolating this pipe, which is necessary to install the new valve in the 36-inch raw water suction line.

This amount compensates the contractor for labor, equipment, and materials to install the line stop, and other related work, as well as inclusion of a credit for removing the scope associated with replacement of the 36in/72in sluice gate at Barton Hydroelectric Facility. The total amount for this item is \$38,029.00.

3. Custom Steel Fitting (PCO 960006): The Waukesha gas-powered pump is used as emergency back-up in the event of power loss to Barton Pump station. The existing fitting from the raw water suction header to this pump was identified for replacement based on further evaluation of the condition as well as the complexity in completing adjacent work without compromising its integrity.

This amount compensates the contractor for labor, equipment, and materials to remove and replace this fitting, and other related work. The total amount for this item is \$66,049.00.