


RACQUET CLUB OF ANN ARBOR PUMP HOUSE & SITE RENOVATION

3010 HICKORY LANE, CITY OF ANN ARBOR, WASHTENAW COUNTY, MICHIGAN 48104 SITE PLAN ADMINISTRATIVE AMENDMENT CITY SUBMITTAL 2 - JULY 9, 2021



VICINITY MAP
SCALE : NTS
SECTION 26, T2S, R6E

OWNER

RACQUET CLUB OF ANN ARBOR
3010 HICKORY LANE
ANN ARBOR, MI 48108
ATTN: BRENT SCHOMAKER
734-216-0579

ARCHITECT

MITCHELL AND MOUAT ARCHITECTS
113 SOUTH FOURTH AVE.
ANN ARBOR, MI 48104
ATTN: JOHN MOUAT
734-662-6070

ENGINEER/SURVEYOR

MIDWESTERN CONSULTING, LLC
3815 PLAZA DR.
ANN ARBOR, MI 48108
CONTACT: JEREMY MATTHEI, PE
734-995-0200

ANN ARBOR RACQUET CLUB Narrative Description

I. DEVELOPMENT PROGRAM SUMMARY

The Racquet Club of Ann Arbor is a tennis and swim club that began in the mid 1960's and is located at 3010 Hickory Lane at the southwest corner of Geddes and Huron Parkway. Facilities at the club include clay and all weather tennis courts, a full size pool, tennis locker rooms, office and pro shop, children's pool, playground amenities and grilling and food vending. The facility is open seasonally during daylight hours only. A previous Administrative Amendment in 2015 provided for the reconstruction of the tennis building and outdoor grill.

This proposal contained within this submittal includes the demolition of the existing pump building and replacing it with a new 935 SF pump building. This work will remove the existing pool outlet's sanitary sewer connection, treat the water in the pump building, and direct it to the stormwater infiltration tanks. Also included is the replacement of parts of the pool deck, retaining wall replacement, the addition of a paved rear access to the pump house and pool deck and the addition of an open-air spa tub, and miscellaneous utility installation.

A. Proposed Land Use

The Racquet Club of Ann Arbor will continue to operate as a private tennis, swim and recreational facility.

B. Phasing and Construction Cost

- (B.1) Preliminary Phasing: All construction shall be completed in one phase beginning in the fall of 2021 and being completed in the spring of 2022.
- (B.2) Preliminary Cost Estimate: The combined estimated total project construction cost, including utilities, structures, landscaping and site amenities is approximately \$1.0 million.

1. Community Analysis

- (a) Impact on Schools

The project will have no impact on the school system.

- (b) Relationship with Neighboring Uses

The proposal is consistent with the existing use at this site and should present no objection to neighboring uses.

- North of Site:** The north side of the site is Geddes Road leading down to the Huron River.
- West of Site:** Hickory Lane lies west of the site and serves adjacent residential properties that were developed after the club was established.
- South of Site:** Contains the Huron Hills Golf course.
- East of Site:** Contains a public ROW for what once was the entrance from Geddes Road onto south bound Huron Parkway. It is now a bike lane.

- (c) Impact on Adjacent Uses

The proposed development will have no negative impact on existing uses around the site and is consistent with the current use.

- (d) Impact of Development Relevant to Various Issues:

- Air Quality: The proposal will have no impact on air quality.
- Water Quality: The reconstructed parts of this site will be provided with storm water management facilities in accordance with current standards and discharged in accordance with City of Ann Arbor and Washtenaw County Water Resources Commissioner standards. Stormwater will be collected into proposed trench drains that will be tied-in and directed into an existing system constructed in 2016 with spare capacity.
- Natural Features: Sheet 1 of the site plan provide a graphic description of the natural features that are found on the site. Natural features on this site consist solely of landmark trees. The area that is proposed for development is almost entirely existing improvements in the form of buildings and pedestrian improvements. The development program concentrates all of the activities in this area thus eliminating any impact to landmark trees.
- Wetlands: The site contains no wetlands.
- Steep Slopes: the site contains no steep slopes.
- Floodplains: There are no 100 year floodplains or watercourses that will be impacted by the development.
- Endangered Species or Habitat: None known to exist.
- Woodlands: There are no qualifying woodlands on site.
- Solid Waste - Solid waste removal will be contracted privately using the existing facilities.
- There are no historical sites, structures or districts impacted by the proposed development.

2. Site Analysis

- (a) Existing Land Use

The existing land zoning is Agricultural while the use of the parcel is recreational. The land has been utilized in this fashion for decades.

- (b) Site Conditions

The site is shown in the USDA Soil Conservation Service Soil Survey of Washtenaw County to be primarily Boyer series with 0 to 6% slopes. Site vegetation includes almost exclusively planted trees and shrubs and several native landmark trees that will not be affected. Topography ranges from 785 USGS down to 769 USGS. Sheet 1 of the Area Plan graphically depicts the site conditions.

- (c) Natural Features Description

- (i) No endangered species are known to exist on-site.
- (ii) There is no 100-year floodplain on-site.
- (iii) The landmark trees on site are shown on Sheet 1.
- (iv) There are no steep slopes on the site.
- (v) There are no permanent watercourses on-site.
- (vi) There are no wetlands on the site.
- (vii) There are no woodlands on the site.

- (d) Existing Structures

The site contains a managers residence with a detached garage, a pool building a tennis building, a snack shack grill and two barns for storage.

- (e) Access Points

Vehicular: The site has access through two entrances off of Hickory Lane and one off Geddes Road. No other connections to adjacent properties are anticipated.

Pedestrian and Bicycle: There are currently no sidewalks along Geddes Ave. in front of this location and none are proposed due to expected cost and landscape impacts to the screening trees and power poles, however there is a crosswalk leading to a sidewalk on the far side of Geddes Ave. and Geddes Ave. has bike lanes on both sides of the road. In 2016 a sidewalk was added along the east side of Hickory Lane extending from the Geddes Road crosswalk to the northern edge of the southerly drive approach. Sidewalk waivers for the remainder of Hickory Lane and for the South side of Geddes Ave. were obtained for projects in 1997, 2008, and 2015, and we are requesting a renewal of the waiver with this project.

(f) Utilities
Water: Water is received from a public main located in Geddes Road.
Sanitary Sewer: it is unknown where sanitary sewer service is received from.

Storm Sewer: Storm sewer will collect and drain stormwater runoff to a new underground storm water detention and infiltration unit on the site.

- (g) Drainage

All on-site drainage that is equitable to the new improvements will be detained on-site until it is discharged in accordance with City of Ann Arbor and Washtenaw County Water Resources Commissioner standards. The stormwater discharges to a central storm sewer which will divert the flow into an underground detention and infiltration chamber. The proposed drainage system will be completely internal to the site and utilize sheet flow, underground storm sewer and swirl separators that filter the stormwater and release the runoff at a pre-developed rate of discharge.

3. Traffic Impact

The scope of this project includes the reconstruction of existing facilities only. No new uses or expansion of existing uses is proposed therefore no new trip generation is expected.

GENERAL NOTES:

PER CHAPTER 49, SECTION 4:58 OF THE CITY CODE, "ALL SIDEWALKS SHALL BE KEPT AND MAINTAINED IN GOOD REPAIR BY THE OWNER OF THE LAND ADJACENT TO AND ABUTTING THE SAME. PRIOR TO THE ISSUANCE OF THE FINAL CERTIFICATE OF OCCUPANCY FOR THIS SITE, ALL EXISTING SIDEWALKS IN NEED OF REPAIR MUST BE REPAIRED IN ACCORDANCE WITH CITY STANDARDS."

THE CONSTRUCTION COVERED BY THESE PLANS SHALL CONFORM TO THE CITY OF ANN ARBOR PUBLIC SERVICES DEPARTMENT STANDARD SPECIFICATIONS.


THE CONSTRUCTION COVERED BY THESE PLANS SHALL CONFORM TO THE CITY OF ANN ARBOR PUBLIC SERVICES DEPARTMENT STANDARD DETAILS.

THE OMISSION OF ANY STANDARD DETAILS DOES NOT RELIEVE THE CONTRACTORS OF THEIR OBLIGATION TO CONSTRUCT ITEMS IN COMPLETE ACCORDANCE WITH PUBLIC SERVICES DEPARTMENT STANDARD SPECIFICATIONS.

LINE STOPS SHALL BE INSTALLED WHERE EXISTING WATER MAINS CANNOT BE SUFFICIENTLY ISOLATED TO COMPLETE THE WORK. THE COST OF ANY LINE STOP INSTALLATION IS THE RESPONSIBILITY OF THE DEVELOPER AND/OR CONTRACTOR.

PAVEMENT MARKINGS DISTURBED AS A RESULT OF PAVEMENT CUTS OR CONSTRUCTION ACTIVITIES SHALL BE REPLACED AS DIRECTED BY PROJECT MANAGEMENT. REPLACEMENT DURING CONSTRUCTION OF THE PROJECT MAY BE CONSIDERED TEMPORARY, WITH FINAL PAVEMENT MARKING RESTORATION TO OCCUR AT THE END OF THE PROJECT.

THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PROTECT THE EXISTING ROAD PAVEMENT. DAMAGE TO THE PUBLIC ROAD PAVEMENT DURING THE COURSE OF CONSTRUCTION MAY NECESSITATE MILLING AND RESURFACING OF THE DAMAGED AREAS PRIOR TO ISSUANCE OF THE CERTIFICATE OF OCCUPANCY.



SITE MAP

SCALE : 1"=80'



Sheet List Table


| SHEET NUMBER | SHEET TITLE |
|--------------|--|
| C1.0 | COVER SHEET |
| C1.1 | ALTA TOPOGRAPHIC SURVEY |
| C1.2 | DEMOLITION PLAN |
| C2.0 | OVERALL SITE PLAN |
| C2.1 | FIRE SAFETY PLAN & TRASH TRUCK MOVEMENTS |
| C2.2 | LAYOUT & MATERIALS PLAN - NORTH |
| C2.3 | LAYOUT & MATERIALS PLAN - SOUTH |
| C2.4 | GRADING PLAN - NORTH |
| C2.5 | GRADING PLAN - SOUTH |
| C2.6 | PAVING AND SITE DETAILS |
| C2.7 | DUMPSTER ENCLOSURE AND BOLLARD DETAILS |
| C2.8 | RETAINING WALL DETAILS |
| C3.0 | UTILITY PLAN |
| C3.1 | STORM & SANITARY PLAN & PROFILES |
| C3.2 | WATER LEAD PLAN & PROFILE |
| C3.3 | UTILITY DETAILS |
| C3.4 | TRENCH DRAIN DETAILS |
| C4.0 | STORMWATER PLAN |
| C4.1 | STORM CALCULATIONS |
| C4.2 | 2016 PROJECT - STORMWATER PLAN |
| C4.3 | 2016 PROJECT - STORMWATER CALCS |
| C5.0 | SOIL EROSION CONTROL PLAN |
| C5.1 | SOIL EROSION CONTROL NOTES AND DETAILS |
| L1.0 | OVERALL LANDSCAPE PLAN |
| L2.0 | LANDSCAPE NOTES AND DETAILS |

RACQUET CLUB OF ANN ARBOR

| | | |
|----------------------|---------------------|-------------|
| JOB No. 20213 | DATE: 7/8/2021 | C1.0 |
| ISSUES: | SHEET 1 OF 25 | |
| CITY SUBMITTAL 1 | REV. DATE: 06/07/21 | |
| CITY SUBMITTAL 2 | 07/09/21 | |
| | ENG: JAM | |
| | PM: SWB | |
| | TECH: /20213CV1 | |

MIDWESTERN CONSULTING
3815 Plaza Drive Ann Arbor, Michigan 48108
(734) 995-0200 • www.midwesternconsulting.com
Land Development • Land Survey • Institutional • Municipal
Wireless Communications • Transportation • Landfill Services

| RELEASED FOR: | DATE |
|------------------|----------|
| CITY SUBMITTAL 1 | 6/7/2021 |
| CITY SUBMITTAL 2 | 7/8/2021 |
| | |
| | |
| | |
| | |
| | |



JEREMY A. MATTHEI
P.E.# 62020 53590

LEGAL DESCRIPTION

Commencing at the S.W. corner of Section 26, T2S, R6E, City of Ann Arbor, Washtenaw County, Michigan, thence N 00°00'00" E 515.92 feet along the west line of said Section 26, thence S 71°47'25" E 372.52 feet along the centerline of Geddes Ave. (formerly Huron River Drive); thence S 18°12'35" W 33.00 to the POINT OF BEGINNING,

thence S 71°47'25" E 316.32 feet, thence along the westerly right-of-way line of Huron Parkway in the following two (2) courses:

southeasterly 259.70 feet in the arc of a circular curve to the right, radius 290.00 feet, central angle 51°18'35", chord S 33°59'10" E 251.11 feet, southeasterly 423.76 feet in the arc of a circular curve to the left, radius 1516.47 feet, central angle 16°00'38", chord S 16°20'21" E 422.38 feet,

thence S 59°28'15" W 57.70 feet, thence S 85°38'40" W 283.09 feet, thence S 30°36'31" E 253.37 feet to the S.E. corner of Lot 47 of Riverside Hills Subdivision No. 2, Liber 17 of Plats, Pages 25 and 26, Washtenaw County Records; thence N 89°36'10" W 186.09 feet along the south line of said Lot 47, thence along the easterly right-of-way line of Hickory Lane in the following six (6) courses:

northerly 124.27 feet along the arc of a circular curve to the left, radius 202.38 feet, central angle 35°10'52", chord N 06°54'34" W 122.32 feet, N 24°30'00" W 220.47 feet, northerly 60.54 feet along the arc of a circular curve to the right, radius 110.45 feet, central angle 31°24'12", chord N 08°46'37" W 59.78 feet, N 06°54'35" E 315.97 feet, northerly 63.11 feet along the arc of a circular curve to the right, radius 320.00 feet, central angle 11°18'00", chord N 12°33'35" E 63.01 feet, N 18°12'35" E 28.87 feet to the N.W. corner of Lot 51 of said Riverside Hills Subdivision No. 2, and a part of the S.W. 1/4 of Section 35, T2S, R6E, City of Ann Arbor, Washtenaw County, Michigan, containing 7.72 acres of land more or less, subject to easements and restrictions of record, if any.

Subject to:

Grant of an Easement to the City of Ann Arbor recorded in Liber 5168, Page 27, Washtenaw County Records.


Grant of an Easement to the City of Ann Arbor recorded in Liber 4802, Page 840, Washtenaw County Records.

Grant of an Easement to the City of Ann Arbor recorded in Liber 5168, Page 26, Washtenaw County Records.

Grant of an Easement to the City of Ann Arbor recorded in Liber 5168, Page 28, Washtenaw County Records.

NOTE:

Title work was NOT provided for this survey.




BnB

BnB

BnB

GOLF COURSE





water

TREE LIST

Table with columns: TAG #, DBH, COMMON NAME, GENUS/SPECIES, STEMS, SCORE, LM, DW, REMOVAL. Lists various trees like Honey Locust, Black Pine, White Spruce, etc.

Table with columns: TAG#, COMMON NAME. Lists trees like 138 14" Pine, 139 13" Pine, 140 13" Pine, etc.



LEGEND

- List of symbols and their meanings: -772.2 EXIST. CONTOUR, x772.2 EXIST. SPOT ELEVATION, -o- U.P. EXIST. UTILITY POLE, etc.

NOTES

THE BASE SURVEY WAS PREPARED BY MIDWESTERN CONSULTING IN NOVEMBER 2020. ALL UNDERGROUND UTILITIES AND STRUCTURES HAVE BEEN SHOWN TO A REASONABLE DEGREE OF ACCURACY AND IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THEIR EXACT LOCATION AND TO AVOID DAMAGE THERETO.

BENCHMARKS

- BM#1 - STEAMER VALVE ELEV=769.23 (NAVD88)
BM#2 - STEAMER VALVE ELEV=770.13 (NAVD88)
BM#3 - SPIKE IN UTILITY POLE ELEV=775.70 (NAVD88)
BM#4 - TOP NUT OF HYDRANT ELEV=773.62 (NAVD88)

SOILS DESCRIPTION

BASED ON SOIL SURVEY OF WASHTENAW COUNTY MICHIGAN
BnB - BOYER LOAMY SAND, 0 TO 6 PERCENT SLOPES

SURVEYOR'S CERTIFICATE

To: Racquet Club of Ann Arbor
This is to certify that this map or plat and the survey on which it is based were made in accordance with the 2021 Minimum Standard Detail Requirements for ALTA/NSPS Land Title Surveys, jointly established and adopted by ALTA and NSPS, and includes No Items of Table A thereof. The fieldwork was completed on October 15, 2020.


Date of Plat or Map: June 3, 2021

Patrick L. Hastings, PS 37277




Vertical sidebar containing Midwestern Consulting logo, contact information, and project title: RACQUET CLUB OF ANN ARBOR PUMP HOUSE & SITE RENOVATION SITE PLAN ADMINISTRATIVE AMENDMENT ALTA TOPOGRAPHIC SURVEY. Includes sheet number C1.1 and date 2021.

M:\CIVIL\1304_P\01\20213\Detailed\eng\20213051.dwg, 7/9/2021 4:47 PM, Jeremy A. Matthei, C1.2 DEMOLITION PLAN, MCLC PDF -P3
 Copyright © 2021, Midwestern Consulting L.L.C. All rights reserved. No part of this drawing may be used or reproduced in any form or by any means, or stored in a database or retrieval system, without prior permission of Midwestern Consulting L.L.C.



NOTES:

1. ALL WATER SYSTEM WORK IS ON PRIVATE MAIN, DOWNSTREAM OF THE METER PIT AT THE NORTH END OF THE SITE.
2. ALL SANITARY AND STORM SEWERS ON SITE ARE PRIVATE SEWERS.
3. GAS AND ELECTRIC SERVICES ENTER THE SITE AND ARE METERED AT AND DISTRIBUTED FROM THE MAIN LOCKER ROOM/ADMINISTRATION BUILDING. WATER ENTERS THE SITE AND HEADS TO A METER PIT, WHICH IS BEING REMOVED WITH THIS PROJECT, AND REPLACED WITH A METER ROOM IN THE NEW PUMP BUILDING. ENSURE THAT WATER SERVICE TO THE REMAINDER OF THE SITE IS MAINTAINED THROUGHOUT CONSTRUCTION. COORDINATE ALL NEW CONNECTIONS AT THE MODIFIED METER/DISTRIBUTION AREA. SEE ARCHITECTURAL, MECHANICAL, ELECTRICAL, AND PLUMBING PLANS FOR FURTHER INFORMATION.
4. SEE BUILDING PLANS FOR EXISTING BUILDING CONDITIONS AND BUILDING DEMOLITION INFORMATION.



LEGEND

| | | |
|----------------------|-----|------------------------------|
| - - - | 772 | EXIST. CONTOUR |
| x 772.2 | | EXIST. SPOT ELEVATION |
| ○ U.P. | | EXIST. UTILITY POLE |
| — | | GUY WIRE |
| OH | | EXIST. OVERHEAD UTILITY LINE |
| * | | EXIST. LIGHT POLE |
| g | | EXIST. GAS LINE |
| w | | EXIST. WATER MAIN |
| h | | EXIST. HYDRANT |
| r | | EXIST. GATE VALVE IN BOX |
| r | | EXIST. STORM SEWER |
| s | | EXIST. CATCH BASIN OR INLET |
| s | | EXIST. SANITARY SEWER |
| p | | SIGN |
| g | | GAS METER |
| post | | POST |
| f | | FENCE |
| t | | SINGLE TREE |
| cloud | | TREE OR BRUSH LIMIT |
| TP-1 | | EXIST. TEST PIT LOCATION |
| △ | | CONTROL PT. |
| ■ (solid) | | REMOVE BUILDING |
| ■ (cross-hatch) | | REMOVE CONCRETE |
| ■ (diagonal lines) | | REMOVE ASPHALT PAVEMENT |
| ■ (horizontal lines) | | REMOVE BRICK |
| ■ (vertical lines) | | REMOVE RETAINING WALL |
| | | REMOVE UTILITY |
| ~~~~~ | | REMOVE FENCE |
| x | | REMOVE TREE |

The underground utilities shown have been located from field survey information and existing records. The surveyor makes no guarantees that the underground utilities shown comprise all such utilities in the area, either in-service or abandoned. The surveyor further does not warrant that the underground utilities shown are in the exact location indicated. Although the surveyor does certify that they are located as accurately as possible from the information available.


MIDWESTERN CONSULTING
 3845 Plaza Drive Ann Arbor, Michigan 48106
 (734) 995-0200 • www.midwesternconsulting.com
 Land Development • Land Survey • Institutional • Municipal
 Wireless Communications • Transportation • Landfill Services

CLIENT
 RACQUET CLUB OF ANN ARBOR
 3010 HICKORY LANE
 ANN ARBOR, MI 48104
 BRENT SCHOMAKER
 734-216-0579


RACQUET CLUB OF ANN ARBOR
 PUMP HOUSE & SITE RENOVATION
 SITE PLAN ADMINISTRATIVE AMENDMENT
 DEMOLITION PLAN

C1.2

| | |
|-------------------------|--------------|
| JOB No. | 20213 |
| DATE | 7/9/2021 |
| SHEET | 3 OF 25 |
| REV. DATE | |
| ISSUED | 06-07-21 |
| CITY SUBMITTAL 1 | CADD: JBB |
| CITY SUBMITTAL 2 | 07-09-21 |
| | ENG: JAM |
| | PM: RCW |
| | TECH: JAW |
| | 20213051.dwg |



- NOTES:**
- NO FIREWALLS ARE PROPOSED OR EXISTING FOR THIS PROJECT.
 - SEE ARCHITECTURAL PLANS FOR ALL WORK RELATED TO BUILDINGS, FROST SLABS, CANOPIES, AND TRELLISES.
 - SEE POOL DESIGN PLANS FOR ALL WORK RELATED TO THE SPA, POOL AND SPA EQUIPMENT, AND POOL AND SPA PIPING.
 - THE PROJECT INTENT IS TO REDEVELOP THE SECTION OF SITE AROUND THE PROPOSED BUILDING AND SPA, AND MINIMIZE THE REMAINDER OF SITE DISTURBANCE TO THAT REQUIRED TO INSTALL UNDERGROUND UTILITIES AND CONSTRUCT RETAINING WALLS, AND TO REBUILD THE TRASH ENCLOSURE. PAVEMENT DISTURBANCE AND RESTORATION IN THESE AREAS MAY VARY SLIGHTLY DEPENDING ON CONSTRUCTION METHODS.
 - WORK SHALL BE COMPLETED IN ACCORDANCE WITH THE CITY OF ANN ARBOR STANDARD SPECIFICATIONS FOR CONSTRUCTION.
 - WORK IS PLANNED FOR THE OFF-SEASON WHEN THE RACQUET CLUB IS CLOSED.
 - THE CONTRACTOR SHALL PROVIDE SHOP DRAWINGS AND MATERIAL SAMPLES FOR ALL FENCE AND GATE COMPONENTS, FOR APPROVAL PRIOR TO INSTALLATION OR DELIVERY TO THE SITE.
 - THE POOL DECK AND SIDEWALKS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE AMERICANS WITH DISABILITIES ACT (ADA). CONSULT WITH THE ENGINEER FOR FURTHER GUIDANCE AND TO DOCUMENT IF COMPLIANCE CANNOT BE ATTAINED IN ANY AREAS.
 - EARTH RETENTION WILL NOT BE REQUIRED OR USED IN THE CITY ROADWAY RIGHT-OF-WAY.
 - THE PORTION OF GEDDES AVENUE FRONTING THIS PROJECT WAS RECENTLY RESURFACED, WITH A STREET CUT MORATORIUM IN PLACE UNTIL 2022.
 - AT PRESENT, THE SOUTHERLY HICKORY LANE DRIVEWAY AND THE GEDDES AVENUE DRIVEWAY DO NOT MEET CURRENT CITY STANDARDS. THEY DO NOT NEED TO BE REPLACED CURRENTLY, BUT IN THE FUTURE, WHEN THE DRIVE APPROACHES ALONG GEDDES AVENUE AND HICKORY LANE REQUIRE REPLACEMENT, THEY MUST BE REBUILT TO THE CITY STANDARDS CURRENT AT THE TIME OF REPLACEMENT.



SCALE: 1" = 30'



LEGEND

- EXIST. CONTOUR
- PROP. CONTOUR
- EXIST. UTILITY POLE
- GUY WIRE
- EXIST. OVERHEAD UTILITY LINE
- EXIST. LIGHT POLE
- EXIST. GAS LINE
- EXIST. WATER MAIN
- EXIST. HYDRANT
- EXIST. GATE VALVE IN BOX
- EXIST. STORM SEWER
- EXIST. CATCH BASIN OR INLET
- EXIST. SANITARY SEWER
- SIGN
- GAS METER
- POST
- FENCE
- SINGLE TREE
- TREE OR BRUSH LIMIT
- EXIST. TEST PIT LOCATION
- CONTROL PT.
- CONCRETE
- 3.5" ASPHALT PAVEMENT
- PROP. STORM SEWER
- PROP. CATCH BASIN OR INLET

SITE DATA ANALYSIS

I. Site Use

| | |
|-------------------------------------|------------------|
| Existing Zoning | AG |
| Proposed Zoning | AG |
| Gross Site Area | 7.86 Acres |
| Total Net Site Area | 7.86 Acres |
| Number of Units | 1 |
| Space Use Summary | |
| Managers Residence (GFA) | 1,420 SF |
| Locker Room/Administration Building | 3,638 SF |
| Snack Shack | 851 SF |
| Tennis Building | 3,533 SF |
| New Pump House Building | 935 SF |
| Total | 10,377 SF |

II. Zoning Comparison Information

| | Required | Provided |
|--------------------------------|---------------|------------|
| Minimum Area per Dwelling Unit | 100,000 SF | 342,382 SF |
| Front Setback (Min./Max.)* | 30/40 FT | 40.4 |
| Rear Setback | 50 FT | 266.6 |
| Side Setback (South) | 10% LOT WIDTH | 587.6 |
| EQUALS 51 FT | | |
| Maximum Building Height | 30 FT | 22.5 FT |
| Minimum Lot Size | 100,000 SF | 342,382 SF |
| Minimum Lot Width | 200 FT | 515 FT |
| * To Building walls | | |

III. Parking Requirements

| | Required | Provided |
|-------------------------------|----------|----------|
| 1 space per 200 SF required = | 52 | 55 |
| Barrier Free spaces | 3 | 5 |
| 1 bicycle space per 1000 SF | 11 | 12 |
| 100% CL C | 11 | 12 |

MIDWESTERN CONSULTING
 3845 Plaza Drive Ann Arbor, Michigan 48108
 (734) 995-0200 • www.midwesternconsulting.com
 Land Development • Land Survey • Institutional • Municipal
 Wireless Communications • Transportation • Landfill Services

CLIENT
 RACQUET CLUB OF ANN ARBOR
 3010 HICKORY LANE
 ANN ARBOR, MI 48104
 BRENT SCHOMAKER
 734-216-0579


RACQUET CLUB OF ANN ARBOR
 PUMP HOUSE & SITE RENOVATION
 SITE PLAN ADMINISTRATIVE AMENDMENT
 OVERALL SITE PLAN

C2.0

| | |
|---------------------|---------------|
| DATE: 7/7/2021 | SHEET 4 OF 25 |
| REV. DATE: 06-07-21 | CADD: JBB |
| ISSUED: 07-09-21 | ENG: JAM |
| CITY SUBMITTAL 1 | PM: RCW |
| CITY SUBMITTAL 2 | TECH: RCW |
| | 2021 CSP1.dwg |

The underground utilities shown have been located from field survey information and existing records. The surveyor makes no guarantees that the underground utilities shown comprise all such utilities in the area, either in-service or abandoned. The surveyor further does not warrant that the underground utilities shown are in the exact location indicated. Although the surveyor does certify that they are located as accurately as possible from the information available.

MA:\CIVIL\324_Proj\20213\Detailed\Engineer\20213SP3.dwg, 7/9/2021 4:48 PM, Jeremy A. Matthei, C2.1 FIRE SAFETY PLAN & TRASH TRUCK MOVEMENTS, MCLLC PDF, .pc3
 Copyright © 2021, Midwestern Consulting L.L.C. All rights reserved. No part of this drawing may be used or reproduced in any form or by any means, or stored in a database or retrieval system, without prior permission of Midwestern Consulting L.L.C.




SCALE: 1" = 30'
 0 30 60 90




Know what's below.
 Call before you dig.

LEGEND


- w- EXIST. WATER MAIN
- ⊕ EXIST. HYDRANT
- ⊕ EXIST. GATE VALVE IN BOX
- ⊕^{scb} SPRINKLER CONTROL BOX
- POST
- - - FENCE
- SINGLE TREE
- ⊕^{TP-1} EXIST. TEST PIT LOCATION
- ▭ CONCRETE
- ▭ 3.5" ASPHALT PAVEMENT




SPH-100 Aerial Fire Truck 46.1'
 Overall Length 46.100ft
 Overall Width 6.800ft
 Overall Body Height 11.299ft
 Min Body Ground Clearance 1.080ft
 Max Track Width 6.543ft
 Lock-to-lock time 6.00s
 Max Steering Angle (Virtual) 36.30°



Xpeditor Garbage Truck
 Overall Length 28.250ft
 Overall Width 6.833ft
 Overall Body Height 10.525ft
 Min Body Ground Clearance 3.978ft
 Track Width 6.250ft
 Lock-to-lock time 6.00s
 Curb to Curb Turning Radius 32.905ft



FIRE SAFETY PLAN



TRASH TRUCK TURNING MOVEMENT

The underground utilities shown have been located from field survey information and existing records. The surveyor makes no guarantees that the underground utilities shown comprise all such utilities in the area, either in-service or abandoned. The surveyor further does not warrant that the underground utilities shown are in the exact location indicated. Although the surveyor does certify that they are located as accurately as possible from the information available.

MIDWESTERN CONSULTING
 3815 Plaza Drive Ann Arbor, Michigan 48108
 (734) 995-0200 • www.midwesternconsulting.com
 Land Development • Land Survey • Institutional • Municipal
 Wireless Communications • Transportation • Landfill Services

CLIENT
 RACQUET CLUB OF ANN ARBOR
 3010 HICKORY LANE
 ANN ARBOR, MI 48104
 BRENT SCHOMAKER
 734-216-0579

RACQUET CLUB OF ANN ARBOR
 PUMP HOUSE & SITE RENOVATION
 SITE PLAN ADMINISTRATIVE AMENDMENT
 FIRE SAFETY PLAN & TRASH TRUCK MOVEMENTS


C2.1




JOB No. 20213

DATE: 7/6/2021
ISSUED: 06-07-21
CITY SUBMITTAL 1: 07-09-21
CITY SUBMITTAL 2: 20213SP3.dwg

DATE: 7/6/2021
SHEET 5 OF 25
REV. DATE: CADD: JBB
07-09-21: ENG: JAM
PM: RCW
TECH:
20213SP3.dwg

M:\Civil\132_P\132_P\2021\392\392.dwg, 7/9/2021 4:48 PM, Jeremy A. Matthei, C2.2 LAYOUT & MATERIALS PLAN - NORTH, MCLC PDF - P3
 Copyright © 2021, Midwestern Consulting L.L.C. All rights reserved. No part of this drawing may be used or reproduced in any form or by any means, or stored in a database or retrieval system, without prior permission of Midwestern Consulting L.L.C.




 SCALE: 1" = 10'


 Know what's below.
 Call before you dig.

LEGEND

| | |
|--|------------------------------|
| | EXIST. CONTOUR |
| | PROP. CONTOUR |
| | EXIST. UTILITY POLE |
| | GUY WIRE |
| | EXIST. OVERHEAD UTILITY LINE |
| | EXIST. LIGHT POLE |
| | EXIST. GAS LINE |
| | EXIST. WATER MAIN |
| | EXIST. HYDRANT |
| | EXIST. GATE VALVE IN BOX |
| | EXIST. STORM SEWER |
| | EXIST. CATCH BASIN OR INLET |
| | EXIST. SANITARY SEWER |
| | SIGN |
| | GAS METER |
| | POST |
| | FENCE |
| | SINGLE TREE |
| | TREE OR BRUSH LIMIT |
| | EXIST. TEST PIT LOCATION |
| | CONTROL PT. |
| | PROP. TELEPHONE LINE |
| | PROP. ELECTRIC LINE |
| | PROP. STORM SEWER |
| | PROP. CATCH BASIN OR INLET |
| | PROP. WATER MAIN |
| | PROP. SANITARY SEWER |
| | PROP. CLEANOUT |
| | CONCRETE |
| | 3.5" ASPHALT PAVEMENT |

NOTE: TRENCH DRAIN SHALL BE ACODRAIN K100 4" WIDE ADA TRENCH DRAIN WITH 465D STAINLESS STEEL ADA GRATE - CLASS 'C' LOADING (1,150 PSI)
 PICKET FENCE SHALL BE HARTFORD GREEN 6' HEIGHT ALUMINUM COMMERCIAL-GRADE

The underground utilities shown have been located from field survey information and existing records. The surveyor makes no guarantees that the underground utilities shown comprise all such utilities in the area, either in-service or abandoned. The surveyor further does not warrant that the underground utilities shown are in the exact location indicated. Although the surveyor does certify that they are located as accurately as possible from the information available.

MIDWESTERN CONSULTING
 3815 Plaza Drive Ann Arbor, Michigan 48108
 (734) 995-0300 • www.midwesternconsulting.com
 Land Development • Land Survey • Institutional • Municipal
 Wireless Communications • Transportation • Landfill Services



CLIENT
 RACQUET CLUB OF ANN ARBOR
 3010 HICKORY LANE
 ANN ARBOR, MI 48104
 BRENT SCHOMAKER
 734-216-0579

RACQUET CLUB OF ANN ARBOR
 PUMP HOUSE & SITE RENOVATION
 SITE PLAN ADMINISTRATIVE AMENDMENT
 LAYOUT & MATERIALS PLAN - NORTH

C2.2

| | |
|---------------------|---------------|
| DATE: 7/7/2021 | SHEET 6 OF 25 |
| REV. DATE: 06-07-21 | CADD: JBB |
| 07-09-21 | ENG: JAM |
| | PK: RCW |
| | TECH: RCW |
| | 2021392.dwg |

M:\Civil\132_Proj\2021\30213\Detail\Engineer\20213021.dwg, 7/9/2021 4:48 PM, Jeremy A. Matthei, C2.3 LAYOUT & MATERIALS PLAN - SOUTH, MCLC PDF - P.3
Copyright © 2021, Midwestern Consulting L.L.C. All rights reserved. No part of this drawing may be used or reproduced in any form or by any means, or stored in a database or retrieval system, without prior permission of Midwestern Consulting L.L.C.



SCALE: 1" = 10'
0 10 20 30



LEGEND

- 772 ——— EXIST. CONTOUR
- 772 - - - PROP. CONTOUR
- o- U.P. EXIST. UTILITY POLE
- GUY WIRE
- OH ——— EXIST. OVERHEAD UTILITY LINE
- * ——— EXIST. LIGHT POLE
- g ——— EXIST. GAS LINE
- w ——— EXIST. WATER MAIN
- EXIST. HYDRANT
- EXIST. GATE VALVE IN BOX
- r ——— EXIST. STORM SEWER
- EXIST. CATCH BASIN OR INLET
- - - EXIST. SANITARY SEWER
- SIGN
- GAS METER
- POST
- FENCE
- SINGLE TREE
- TREE OR BRUSH LIMIT
- TP-1 EXIST. TEST PIT LOCATION
- △ CONTROL PT.
- T ——— PROP. TELEPHONE LINE
- E ——— PROP. ELECTRIC LINE
- CONCRETE
- 3.5" ASPHALT PAVEMENT

NOTE: TRENCH DRAIN SHALL BE ACODRAIN K100 4" WIDE ADA TRENCH DRAIN WITH 465D STAINLESS STEEL ADA GRATE - CLASS 'C' LOADING (1,150 PSI)



CLIENT
RACQUET CLUB OF ANN ARBOR
3010 HICKORY LANE
ANN ARBOR, MI 48104
BRENT SCHOMAKER
734-216-0579



RACQUET CLUB OF ANN ARBOR
PUMP HOUSE & SITE RENOVATION
SITE PLAN ADMINISTRATIVE AMENDMENT
LAYOUT & MATERIALS PLAN - SOUTH

C2.3

| | |
|--------------|----------|
| JOB No. | 20213 |
| DATE: | 7/7/2021 |
| SHEET | 7 OF 25 |
| REV. DATE | 06-07-21 |
| CADD. | JAM |
| ENG. | JAM |
| PM. | RCW |
| TECH. | RCW |
| 20213SP2.dwg | |

The underground utilities shown have been located from field survey information and existing records. The surveyor makes no guarantees that the underground utilities shown comprise all such utilities in the area, either in-service or abandoned. The surveyor further does not warrant that the underground utilities shown are in the exact location indicated. Although the surveyor does certify that they are located as accurately as possible from the information available.

M:\Civ\132_Proj\2021\3\Detailed\Engineer\2021\3\01.dwg, 7/9/2021 4:49 PM, Jeremy A. Matthei, C2.5 GRADING PLAN - SOUTH, MCLC PDF.ppt
 Copyright © 2021, Midwestern Consulting L.L.C. All rights reserved. No part of this drawing may be used or reproduced in any form or by any means, or stored in a database or retrieval system, without prior permission of Midwestern Consulting L.L.C.



SCALE: 1" = 10'



LEGEND

| | | |
|--|-------------|------------------------------|
| | 772 | EXIST. CONTOUR |
| | 772 | PROP. CONTOUR |
| | 772.2 | EXIST. SPOT ELEVATION |
| | 772.20x | PROP. SPOT ELEVATION |
| | u.p. | EXIST. UTILITY POLE |
| | G | GUY WIRE |
| | OH | EXIST. OVERHEAD UTILITY LINE |
| | * | EXIST. LIGHT POLE |
| | g | EXIST. GAS LINE |
| | w | EXIST. WATER MAIN |
| | H | EXIST. HYDRANT |
| | B | EXIST. GATE VALVE IN BOX |
| | r | EXIST. STORM SEWER |
| | I | EXIST. CATCH BASIN OR INLET |
| | S | EXIST. SANITARY SEWER |
| | P | SIGN |
| | M | GAS METER |
| | POST | POST |
| | FENCE | FENCE |
| | TREE | SINGLE TREE |
| | | TREE OR BRUSH LIMIT |
| | TP-1 | EXIST. TEST PIT LOCATION |
| | CONTROL PT. | CONTROL PT. |
| | T | PROP. TELEPHONE LINE |
| | E | PROP. ELECTRIC LINE |
| | | CONCRETE |
| | | 3.5" ASPHALT PAVEMENT |

MIDWESTERN CONSULTING
 385 Plaza Drive Ann Arbor, Michigan 48108
 (734) 995-0200 • www.midwesternconsulting.com
 Land Development • Land Survey • Institutional • Municipal
 Wireless Communications • Transportation • Landfill Services



CLIENT
 RACQUET CLUB OF ANN ARBOR
 3010 HICKORY LANE
 ANN ARBOR, MI 48104
 BRENT SCHOMAKER
 734-216-0579


RACQUET CLUB OF ANN ARBOR
 PUMP HOUSE & SITE RENOVATION
 SITE PLAN ADMINISTRATIVE AMENDMENT
 GRADING PLAN - SOUTH

C2.5


| | |
|-------------------------|----------|
| JOB No. | 20213 |
| DATE: | 7/6/2021 |
| REV. DATE | |
| ISSUED: | 06-07-21 |
| CITY SUBMITTAL 1 | |
| CITY SUBMITTAL 2 | |
| DATE: | 7/6/2021 |
| SHEET | 9 OF 25 |
| CADD: | JB |
| ENG.: | JAM |
| PM: | RCW |
| TECH: | RCW |
| 20213SP1.dwg | |

The underground utilities shown have been located from field survey information and existing records. The surveyor makes no guarantees that the underground utilities shown comprise all such utilities in the area, either in-service or abandoned. The surveyor further does not warrant that the underground utilities shown are in the exact location indicated. Although the surveyor does certify that they are located as accurately as possible from the information available.


M:\Civ\130_Proj\2021\301\det\1\2021\301\01.dwg, 7/9/2021 4:49 PM, Jeremy A. Matthei, C2.6 PAVING AND SITE DETAILS, MCLC PDF -p3
 Copyright © 2021, Midwestern Consulting L.L.C. All rights reserved. No part of this drawing may be used or reproduced in any form or by any means, or stored in a database or retrieval system, without prior permission of Midwestern Consulting L.L.C.




| | | | | |
|-----------------------------|--|-----------------------------------|----------------|---------------------------------|
| EFF-20 COMMERCIAL | 6' HIGH 3-RAIL ALUMINUM FENCE PANEL | CONTRACTOR: | COLOR: | 50925 RICHARD W. BLVD |
| | 1-1-16 V. 1.0 TKS 1 KS 1 STD DRWG | 1-1-16 V. 1.0 TKS 1 KS 1 STD DRWG | HARTFORD GREEN | CHESTERFIELD TOWNSHIP, MI 48051 |
| | ELITE FENCE PRODUCTS, INC. www.elitefence.com | | | 1-800-783-1331 |




18" MDOT F2 CONCRETE BARRIER CURB AND GUTTER
1"=1' MODIFIED FOR 5.0% GUTTER CROSS-SLOPE




BITUMINOUS PAVEMENT DETAIL (PARKING LOT)
NOT TO SCALE




CONCRETE SIDEWALK AND POOL DECK DETAIL
NOT TO SCALE




UNILOCK PAVER SECTION
NOT TO SCALE



CONCRETE STAIR DETAILS
NOT TO SCALE




SCREEN FENCE DETAIL
NOT TO SCALE



8" CONCRETE PAVEMENT DETAIL
SCALE: 1"=1'


| | | | | | |
|---|---|---|-------------|------------------|---------------------|
| MIDWESTERN CONSULTING 3845 Plaza Drive Ann Arbor, Michigan 48108 (734) 995-0300 • www.midwesternconsulting.com Land Development • Land Survey • Institutional • Municipal Wireless Communications • Transportation • Landfill Services | CLIENT RACQUET CLUB OF ANN ARBOR 3010 HICKORY LANE ANN ARBOR, MI 48104 BRENT SCHOMAKER 734-216-0579 | RACQUET CLUB OF ANN ARBOR PUMP HOUSE & SITE RENOVATION SITE PLAN ADMINISTRATIVE AMENDMENT PAVING AND SITE DETAILS | C2.6 | DATE: 7/9/2021 | SHEET 10 OF 25 |
| | | | | ISSUED: 06-07-21 | REV. DATE: 07-09-21 |
| JOB No. 20213 | | CITY SUBMITTAL 1 | | CAD: JBB | ENG: JAM |
| CITY SUBMITTAL 2 | | FM: JAW | | TECH: RCW | 2021301T.dwg |

M:\Civ\1324_Proj\2021\3071\Det\1.dwg 7/9/2021 4:49 PM, Jeremy A. Matthei, C2.7 DUMPSTER ENCLOSURE AND BOLLARD DETAILS, MCLLC PDF.plt
Copyright © 2021, Midwestern Consulting L.L.C. All rights reserved. No part of this drawing may be used or reproduced in any form or by any means, or stored in a database or retrieval system, without prior permission of Midwestern Consulting L.L.C.




DUMPSTER ENCLOSURE ENLARGEMENT
1"=2'


TRASH & RECYCLING NARRATIVE:
THE RACQUET CLUB OF ANN ARBOR CURRENTLY GENERATES APPROXIMATELY 7 CYD OF TRASH AND 5 CYD OF RECYCLING EACH WEEK, WHICH CAN BE SERVICED WITH A SINGLE WEEKLY PICKUP OF AN 8 CYD TRASH DUMPSTER AND A 6 CYD RECYCLING DUMPSTER. EXTRA PICKUPS ARE ORDERED ON RARE OCCASIONS FOR ADDITIONAL COLLECTION. THESE VALUES WILL NOT CHANGE RESULTING FROM THE WORK IN THIS PROJECT, AND AN 8 CYD TRASH DUMPSTER AND 6 CYD RECYCLING DUMPSTER WILL CONTINUE TO BE ADEQUATE FOR THE PROPERTY.



DUMPSTER ENCLOSURE GATE DETAIL
NOT TO SCALE





DUMPSTER ENCLOSURE WALL SECTION
NOT TO SCALE










PIPE BOLLARD DETAIL
NOT TO SCALE

| | |
|--|--|
| MIDWESTERN CONSULTING | |
| 385 Plaza Drive Ann Arbor, Michigan 48108 (734) 995-0000 • www.midwesternconsulting.com Land Development • Land Survey • Institutional • Municipal Wireless Communications • Transportation • Landfill Services | |
| | |
| CLIENT RACQUET CLUB OF ANN ARBOR 3010 HICKORY LANE ANN ARBOR, MI 48104 BRENT SCHOMAKER 734-216-0579 | |
| RACQUET CLUB OF ANN ARBOR | |
| PUMP HOUSE & SITE RENOVATION SITE PLAN ADMINISTRATIVE AMENDMENT DUMPSTER ENCLOSURE AND BOLLARD DETAILS | |
| C2.7 | |
| JOB No. 20213 ISSUED: _____ CITY SUBMITTAL 1 CITY SUBMITTAL 2 | DATE: 7/9/2021 SHEET 11 OF 25 REV. DATE: _____ REV. DATE: 06-07-21 07-09-21 CADD: JBB ENG: JAM PM: RCW TECH: _____ 20213071.dwg |

Pisa2™



| Bundle Type | Tapered Split | | Corner Dbl Split | Coping |
|--------------------|---------------------------|---------------------------|------------------------|----------|
| | SINGLE | SINGLE | SINGLE | SINGLE |
| | MICHIGAN | MICHIGAN | MICHIGAN | MICHIGAN |
| Thickness (mm) | 150MM | 150MM | 75MM | 75MM |
| Dimension mm | 200mm x 150mm x 300mm | 300mm x 150mm x 200mm | 300mm x 75mm x 300mm | |
| Dimension Imperial | 7 7/8" x 5 7/8" x 11 7/8" | 11 7/8" x 5 7/8" x 7 7/8" | 11 7/8" x 3" x 11 7/8" | |
| FCFT PER | | | | |
| Layer | 20.00 | 20.17 | 20.34 | |
| Stone | 6.67000 | 6.72000 | 2.91000 | |
| | 0.67 | 1.68 | 0.48 | |
| PER BUNDLE | | | | |
| Layers | 3.00 | 3.00 | 7.00 | |
| Sections | 2.00 | 4.00 | 2.00 | |
| LNFT PER | | | | |
| Bundle | 40.00 | - | 82.95 | |
| Unit | 1.33 | - | 1.97 | |
| UNITS PER | | | | |
| SqFt | 1.50 | 0.59 | 2.06 | |
| Section | 15.00 | 3.00 | 21.00 | |
| Bundle | 30.00 | 12.00 | 42.00 | |
| LBS PER | | | | |
| Layer | 600 | 440 | 393 | |
| Section | 1,290 | 330 | 1,375 | |
| Bundle | 2,580 | 1,320 | 2,750 | |




CLASSIC

SIERRA COLOR TO BE USED

RETAINING WALL PRODUCT INFORMATION
NOT TO SCALE

UNLOCK 47

TYPICAL SECTION - NOT FOR CONSTRUCTION



Design Specific Geometric Information

| Retaining Wall System | Pisa2 w Geogrid | Geogrid Type and Manufacturer | See Notes |
|--|-----------------|------------------------------------|--------------------|
| Maximum Height (ft) | 990 (36) | Minimum Geogrid L103 kN/m (8ft) | See Notes |
| Maximum Slope Above Wall | 1V:3H | Maximum Slope Below Wall | None |
| Max. Surcharge Above Wall (kPa) (lb/ft²) | None | Depth of Embankment (ft) | 153 (6) |
| Butter of Wall | 7.12 * | Compacted Base Dimension (mm) (in) | 610 x 153 (24 x 6) |

Design Specific Soil Information

| Description (by USCS) | Soil Region | | | |
|--|--|---|---|--|
| | Infill | Retained | Foundation | Base |
| GW Well graded, free draining Granular | CL Inorganic Clays Low Plasticity | CL Inorganic Clays Low Plasticity | GW Well graded, free draining Granular | see Infill |
| Effective Internal Friction Angle | 35 | 28 | 28 | 39 |
| Moist Unit Weight (kN/m³) (lb/cu.ft) | 22 (140) | 20 (127) | 20 (127) | 22 (140) |
| Effective Cohesion (kPa) (lb/ft²) | NR | NR | NR | NR |
| Soil Notes | Placed in 150mm (6") lifts and compacted to 95% SPD. | Undisturbed dense soil or well compacted Eng. fill. | Allowable bearing cap must exceed 50kPa (1050 psf). | Crushed Gravel (free draining) compacted to 98% SPD. |


NR - Not Required
 Notes:
 1. This design meets or exceeds the minimum factors of safety required by Risi Stone Systems based on the design parameters listed above. The analysis was performed as outlined in the National Concrete Masonry Association Design Manual for Segmental Retaining Walls, Third Edition. This is a typical, non site-specific Design.
 2. No analysis of global stability, total or differential settlement, or seismic effects has been performed.
 3. This design is only provided to illustrate the general arrangement of the SRW structure for preliminary costing and feasibility purposes only. This drawing is not for construction. A qualified Engineer must be retained to provide the Final Design prior to construction.
 4. Structures such as handrails, guardrails, fences, terraces, and site conditions such as water applications, drainage and soil conditions, additional live and dead loads, etc., have significant effects on the wall design and have not been taken into account in this typical section. When accounted for in the Final Design, other conditions and elements may result in additional design measures (geogrid, drainage, etc) and cost.
 5. For geogrid reinforced structures, a minimum Long Term Allowable Design Strength of 14 kN/m was assumed. Contact your manufacturer or Risi Stone Systems for a list of approved geogrid reinforcements.



Pisa 2[®]
 Retaining Wall
 Geogrid Section
 990mm (3.25ft)
 Site: 3H:1V Slope - Clays
 Infill: Granular
 P21RBSAI099

2.5' HIGH WALL SECTION
NOT TO SCALE

TYPICAL SECTION - NOT FOR CONSTRUCTION



Design Specific Geometric Information

| Retaining Wall System | Pisa2 w Geogrid | Geogrid Type and Manufacturer | See Notes |
|--|-----------------|------------------------------------|--------------------|
| Maximum Height (ft) | 1140 (44) | Minimum Geogrid L103 kN/m (8ft) | See Notes |
| Maximum Slope Above Wall | 1V:3H | Maximum Slope Below Wall | None |
| Max. Surcharge Above Wall (kPa) (lb/ft²) | None | Depth of Embankment (ft) | 153 (6) |
| Butter of Wall | 7.12 * | Compacted Base Dimension (mm) (in) | 610 x 153 (24 x 6) |

Design Specific Soil Information

| Description (by USCS) | Soil Region | | | |
|--|--|---|---|--|
| | Infill | Retained | Foundation | Base |
| GW Well graded, free draining Granular | CL Inorganic Clays Low Plasticity | CL Inorganic Clays Low Plasticity | GW Well graded, free draining Granular | see Infill |
| Effective Internal Friction Angle | 35 | 28 | 28 | 39 |
| Moist Unit Weight (kN/m³) (lb/cu.ft) | 22 (140) | 20 (127) | 20 (127) | 22 (140) |
| Effective Cohesion (kPa) (lb/ft²) | NR | NR | NR | NR |
| Soil Notes | Placed in 150mm (6") lifts and compacted to 95% SPD. | Undisturbed dense soil or well compacted Eng. fill. | Allowable bearing cap must exceed 50kPa (1050 psf). | Crushed Gravel (free draining) compacted to 98% SPD. |

NR - Not Required
 Notes:
 1. This design meets or exceeds the minimum factors of safety required by Risi Stone Systems based on the design parameters listed above. The analysis was performed as outlined in the National Concrete Masonry Association Design Manual for Segmental Retaining Walls, Third Edition. This is a typical, non site-specific Design.
 2. No analysis of global stability, total or differential settlement, or seismic effects has been performed.
 3. This design is only provided to illustrate the general arrangement of the SRW structure for preliminary costing and feasibility purposes only. This drawing is not for construction. A qualified Engineer must be retained to provide the Final Design prior to construction.
 4. Structures such as handrails, guardrails, fences, terraces, and site conditions such as water applications, drainage and soil conditions, additional live and dead loads, etc., have significant effects on the wall design and have not been taken into account in this typical section. When accounted for in the Final Design, other conditions and elements may result in additional design measures (geogrid, drainage, etc) and cost.
 5. For geogrid reinforced structures, a minimum Long Term Allowable Design Strength of 14 kN/m was assumed. Contact your manufacturer or Risi Stone Systems for a list of approved geogrid reinforcements.



Pisa 2[®]
 Retaining Wall
 Geogrid Section
 1140mm (3.74ft)
 Site: 3H:1V Slope - Clays
 Infill: Granular
 P21RBSAI114

3.0' HIGH WALL SECTION
NOT TO SCALE



MIDWESTERN CONSULTING
 385 Plaza Drive Ann Arbor, Michigan 48108
 (734) 995-0200 • www.midwesternconsulting.com
 Land Development • Land Survey • Institutional • Municipal
 Wireless Communications • Transportation • Landfill Services


CLIENT
 RACQUET CLUB OF ANN ARBOR
 3010 HICKORY LANE
 ANN ARBOR, MI 48104
 BRENT SCHOMAKER
 734-216-0579

RACQUET CLUB OF ANN ARBOR
 PUMP HOUSE & SITE RENOVATION
 SITE PLAN ADMINISTRATIVE AMENDMENT
 RETAINING WALL DETAILS

C2.8

| | | |
|--------------------------|---------------------|----------------|
| JOB No. 20213 | DATE: 7/7/2021 | SHEET 12 OF 25 |
| ISSUED: CITY SUBMITTAL 1 | REV. DATE: 06-07-21 | CADD: JBB |
| CITY SUBMITTAL 2 | 07-09-21 | ENG: JAM |
| | | PM: RCW |
| | | TECH: JMW |
| | | 20213RWT.dwg |

The underground utilities shown have been located from field survey information and existing records. The surveyor makes no guarantees that the underground utilities shown comprise all such utilities in the area, either in-service or abandoned. The surveyor further does not warrant that the underground utilities shown are in the exact location indicated. Although the surveyor does certify that they are located as accurately as possible from the information available.



- NOTES:**
- ALL PRIVATE WATER MAIN AND LEADS ON THIS SITE ARE DOMESTIC LEADS. NO BUILDINGS HAVE EXISTING OR PROPOSED FIRE SERVICES. A SINGLE METER PIT EXISTS SOUTH OF GEDDES AVENUE, AND EACH BUILDING HAS ITS OWN BACKFLOW PREVENTOR AT THE PIPE ENTRY POINT. HIS METER PIT IS BEING REPLACED WITH A METER ROOM IN THE NEW PUMP BUILDING AS A PART OF THE CONSTRUCTION PROCESS. ENSURE THAT WATER SERVICE TO THE REMAINDER OF THE SITE IS MAINTAINED THROUGHOUT CONSTRUCTION. EXTERIOR WATER LEAD PIPING SHALL BE CLASS 50 DUCTILE IRON PIPE WITH POLYWRAP, PER THE CITY OF ANN ARBOR STANDARD SPECIFICATIONS.
 - ALL SANITARY AND STORM SEWERS ON SITE ARE PRIVATE SEWERS. SANITARY SEWER PIPES AND STORM PIPES SMALLER THAN 12 INCHES SHALL BE SDR 35 PVC. STORM PIPES 12 INCHES OR GREATER SHALL BE N12 HDPE.
 - THE EXISTING AND PROPOSED PUMP HOUSE BUILDINGS DO NOT HAVE ANY FOOTING DRAINS.
 - NO FIRE WALLS ARE EXISTING OR PROPOSED FOR THIS SITE.
 - ELECTRIC SERVICES ENTER THE SITE AND ARE METERED AT AND DISTRIBUTED FROM THE MAIN ADMINISTRATION / LOCKER ROOM BUILDINGS. COORDINATE ALL NEW CONNECTIONS AT THE MODIFIED METER/DISTRIBUTION AREA. SEE ARCHITECTURAL, MECHANICAL, ELECTRICAL, AND PLUMBING PLANS FOR FURTHER INFORMATION.
 - INSTALL POWER AND TELECOM CONDUITS IN SCHEDULE 40 PVC PIPE, WITH 3' COVER. CONDUITS AND HANDHOLES TO BE CONSTRUCTED IN ACCORDANCE WITH THE 2012 MDT STANDARD SPECIFICATIONS FOR CONSTRUCTION. SEE ELECTRICAL PLANS FOR WIRE AND CIRCUIT INFORMATION. INSTALL PULL WIRE WITH ALL CONDUITS.
 - COORDINATE THE GAS LEAD AND METER RELOCATION WITH DTE ENERGY.
 - ALL POWER, TELECOM, AND GAS PIPING CONDUITS TO BE BURIED 3' DEEP, OR DEEPER AS REQUIRED TO CROSS GAS AND OTHER UTILITIES. PARALLEL CONDUITS AND PIPES OF THE SAME UTILITY SHALL BE LAID 12" APART.
 - SEE THE POOL DESIGN DRAWINGS FOR ALL INFORMATION REGARDING PIPING AND EQUIPMENT FOR THE POOL AND SPA.
 - THE EXISTING RACQUET CLUB WATER LEAD IS TAPPED OFF OF THE HYDRANT LEAD ON GEDDES AVENUE, WHICH DOES NOT MEET CURRENT STANDARDS. THE CITY'S ENGINEERING DEPARTMENT IS ALLOWING THIS TO REMAIN IN PLACE UNTIL SUCH TIME THAT THE LEAD REQUIRES REPAIR OR REPLACEMENT AT WHICH TIME THE LEAD MUST BE CONNECTED TO THE 20" LOOPED WATER MAIN IN GEDDES AVE.
 - NOTE ON POOL DECK DRAINAGE:** THIS POOL IS DESIGNED FOLLOWING THE STATE OF MICHIGAN ECLE AND NPDES STANDARDS FOR OUTDOOR POOLS AND DECKS. THE POOL BACKWASH AND DRAINAGE ARE DECHLORINATED BEFORE BEING RELEASED TO THE STORM SYSTEM. WHILE THE POOL DECKS THEMSELVES DRAIN TO A SANITARY SEWER IN AN ENCLOSED POOL, THEY ARE RELEASED AS STORM DRAINAGE IN AN OUTDOOR POOL. THE AMOUNT OF POOL WATER THAT IS RELEASED IS AN EXTREMELY SMALL PORTION OF THE TOTAL RUNOFF (WHEN FACTORING IN RAINFALL), SO THE DECHLORINATION OF POOL DECK WATER IS NOT PRACTICAL, AND IT IS AN OVERALL CHLORINE LEVEL IS BELOW NPDES REQUIREMENTS. THE FOLLOWING CALCULATIONS ARE PROVIDED TO INDICATE THAT THE CHLORINE IMPACTS ARE SUBSTANTIALLY LESS THAN THAT FROM IRRIGATION OR POWER-WASHING USING TAP WATER, OR FIRE HYDRANT FLUSHING WITH TAP WATER AVERAGING 2 PPM OF CHLORINE.
 - SWIMMING POOLS SHOULD BE MAINTAINED WITHIN 1.0-5.0 PPM OF CHLORINE, AND THE RACQUET CLUB KEEPS THE POOL WITHIN THE 2.0-2.5 PPM RANGE. THIS COMPARES FAVORABLY WITH CITY OF ANN ARBOR TAP WATER RANGING FROM 1.0-3.5 PPM IN THE 2020 WATER QUALITY REPORT. FOR COMPARISON, THE EPA ALLOWS DRINKING WATER CHLORINE LEVELS TO BE AS HIGH AS 4.5 PPM, AND THE NPDES DISCHARGE PERMIT FOR THE POOL WATER REQUIRES THE CHLORINE LEVELS TO BE REDUCED TO LESS THAN 0.5 PPM.
 - ASSUMED DECK DRAINAGE WATER: MOST POOL SPLASH WATER EVAPORATES ON THE DECK OR WITHIN THE TRENCH DRAINS. CONSERVATIVELY WE CAN ASSUME 5 GALLONS OF RUNOFF PER HOUR DURING INTENSE TEAM BUTTERFLY AND DIVING PRACTICE, OVER TEN HOURS, FOR A TOTAL OF 50 GALLONS PER DAY, OR 1,500 GALLONS PER MONTH. SOUTHEAST MICHIGAN GENERALLY RECEIVES ABOUT 3 INCHES OF RAIN PER MONTH, WHICH WOULD EQUATE TO 0.25 FT x 10,100 SFT = 2,525 CFT = 18,887 GALLONS OF RAINFALL, OR 20,387 TOTAL GALLONS. THUS THE POOL WATER IS ONLY 7.3% OF THE TOTAL RUNOFF, AND DECHLORINATING IS NOT PRACTICAL AS THE INFRASTRUCTURE DESIGNED TO HANDLE AN INTENSE RAINFALL IS INCOMPATIBLE WITH THE DECHLORINATION INFRASTRUCTURE REQUIRING A SLOW AND STEADY FLOW RATE. LIKEWISE DRAINING THE POOL DECK INTO THE SANITARY SEWER IS NOT ALLOWED BY CITY CODE, AS IT WOULD OVERLOAD THE SANITARY SEWER SYSTEM AND CONTRIBUTE TO COMBINED SEWER OVERFLOWS.
 - USING A CONSERVATIVELY HIGH VALUE OF 5.0 PPM CHLORINE IN THE POOL WATER (THE LEGAL MAXIMUM, DOUBLE THE LEVEL PLANNED BY RACQUET CLUB MANAGEMENT), WITH 50 GALLONS PER DAY OF POOL WATER DISCHARGE ON THE DECK AND 3 INCHES OF RAINFALL FOR THE MONTH, WE GET 1,500 GALLONS/20,387 GALLONS x 5.0 PPM = 0.37 PPM CHLORINE IN THE DISCHARGE. WITH POOL WATER MAINTAINED AT THE TARGET LEVEL OF 2.5 PPM, THIS WOULD REDUCE TO 0.18 PPM, AND GIVEN THE NATURE OF POOL DECK WATER MOSTLY EVAPORATING BEFORE REACHING A DRAIN, THIS VALUE WOULD BE EVEN LESS. THUS EVEN IN A MONTH WITH CHLORINE MAINTAINED AT THE MAXIMUM ALLOWABLE LEVEL, THE NPDES REQUIREMENT OF 0.50 PPM MAXIMUM CHLORINE DISCHARGE WOULD BE MET.
 - FINALLY, THE NATURE OF THE STORMWATER SYSTEM ON THIS PROPERTY WILL INFILTRATE. THESE DRY-WEATHER DISCHARGES INTO THE GROUND, IN MUCH THE SAME WAY AS A SEPTIC SYSTEM DOES. THE DRAINAGE WILL NOT BE RELEASED INTO SURFACE WATERS, AND WILL DECHLORINATE NATURALLY UNDERGROUND AS IT REACHES UNDERGROUND AQUIFERS.
- THIS REPRESENTS STANDARD PRACTICE FOR OUTDOOR POOL DECKS, AND IS APPROVED BY THE STATE OF MICHIGAN - ECLE IN THEIR PERMITS.

LEGEND

| | |
|------|------------------------------|
| 772 | EXIST. CONTOUR |
| 772 | PROP. CONTOUR |
| U.P. | EXIST. UTILITY POLE |
| GUY | GUY WIRE |
| OH | EXIST. OVERHEAD UTILITY LINE |
| * | EXIST. LIGHT POLE |
| g | EXIST. GAS LINE |
| w | EXIST. WATER MAIN |
| H | EXIST. HYDRANT |
| SV | EXIST. GATE VALVE IN BOX |
| r | EXIST. STORM SEWER |
| □ | EXIST. CATCH BASIN OR INLET |
| s | EXIST. SANITARY SEWER |
| △ | SIGN |
| ⊙ | GAS METER |
| • | POST |
| — | FENCE |
| ○ | SINGLE TREE |
| ○ | TREE OR BRUSH LIMIT |
| TP-1 | EXIST. TEST PIT LOCATION |
| △ | CONTROL PT. |
| T | PROP. TELEPHONE LINE |
| E | PROP. ELECTRIC LINE |
| R | PROP. STORM SEWER |
| W | PROP. CATCH BASIN OR INLET |
| S | PROP. WATER MAIN |
| S | PROP. SANITARY SEWER |
| ○ | PROP. CLEANOUT |

SANITARY SEWER MITIGATION CALCULATIONS:


SWIMMING POOL:
 EXISTING BACKWASH PEAK FLOW TO SANITARY SEWER: 600 GPM
 PROPOSED BACKWASH TO BE TREATED AND RELEASED TO STORM SEWER.
 600 GPM PEAK FLOW REDUCTION TO SANITARY SEWER.

NEW SPA:
 ALL BACKWASH AND DRAINAGE TO BE TREATED AND RELEASED TO THE STORM SEWER.
 0 GPM

BUILDING RECONSTRUCTION:
 THIS BUILDING WILL HAVE A SINGLE-OCCUPANCY BATHROOM, AND WILL CALCULATE THE SANITARY FLOWS USING THE SPA/COUNTRY CLUB VALUES FROM THE CITY'S TABLE A:

935 SFT x 0.30 GPD/SFT = 280.5 GPD
 PEAK FLOW = 280.5 GPD x 4 [PEAKING FACTOR] x 1.1
 [SYSTEM RECOVERY FACTOR] = 1,234.2 GPD
 1,234.2 GPD x 1 DAY/24HR x 1 HR/60 MIN = 0.857 GPM

CHANGE RESULTING FROM PROJECT:
 -600 GPM + 0.857 GPM = -599.143 GPM
 ROUND TO A 599 GPM DECREASE.



MIDWESTERN CONSULTING
 3845 Plaza Drive Ann Arbor, Michigan 48108
 (734) 995-0200 • www.midwesternconsulting.com
 Land Development • Land Survey • Institutional • Municipal
 Wireless Communications • Transportation • Landfill Services

CLIENT
 RACQUET CLUB OF ANN ARBOR
 3010 HICKORY LANE
 ANN ARBOR, MI 48104
 BRENT SCHOMAKER
 734-216-0579



20213
 JOB No. 20213
 DATE: 7/9/2021
 SHEET 13 OF 25
 REV. DATE: 06-07-21
 CADD: JBB
 CITY SUBMITTAL 1
 ISSUED: 07-09-21
 ENG: JAM
 CITY SUBMITTAL 2
 PM: RCW
 TECH: JAW
 20213UP1.dwg

UTILITY PLAN
 PUMP HOUSE & SITE RENOVATION
 SITE PLAN ADMINISTRATIVE AMENDMENT

M:\Civil\132_P\1320213\0213001.dwg
 Engineer: ing\20213\01.dwg
 7/9/2021 4:50 PM, Jeremy A. Matthei, C.S.O. UTILITY PLAN, MCLC PDF #43
 Copyright © 2021, Midwestern Consulting L.L.C. All rights reserved. No part of this drawing may be used or reproduced in any form or by any means, or stored in a database or retrieval system, without prior permission of Midwestern Consulting L.L.C.

The underground utilities shown have been located from field survey information and existing records. The surveyor makes no guarantees that the underground utilities shown comprise all such utilities in the area, either in-service or abandoned. The surveyor further does not warrant that the underground utilities shown are in the exact location indicated. Although the surveyor does certify that they are located as accurately as possible from the information available.

M:\Civil\134_Prop\2021\302\302.dwg, 7/9/2021 4:50 PM, Jeremy A. Matthei, C3.1 STORM & SANITARY PLAN & PROFILES, MCLLC PDF, ps3
 Copyright © 2021, Midwestern Consulting L.L.C. All rights reserved. No part of this drawing may be used or reproduced in any form or by any means, or stored in a database or retrieval system, without prior permission of Midwestern Consulting L.L.C.






SCALE: 1" = 20'



LEGEND


- EXIST. CONTOUR
- PROP. CONTOUR
- EXIST. UTILITY POLE
- GUY WIRE
- EXIST. OVERHEAD UTILITY LINE
- EXIST. LIGHT POLE
- EXIST. GAS LINE
- EXIST. WATER MAIN
- EXIST. HYDRANT
- EXIST. GATE VALVE IN BOX
- EXIST. STORM SEWER
- EXIST. CATCH BASIN OR INLET
- EXIST. SANITARY SEWER
- SIGN
- GAS METER
- POST
- FENCE
- SINGLE TREE
- TREE OR BRUSH LIMIT
- EXIST. TEST PIT LOCATION
- CONTROL PT.
- PROP. TELEPHONE LINE
- PROP. ELECTRIC LINE
- PROP. STORM SEWER
- PROP. CATCH BASIN OR INLET
- PROP. WATER MAIN
- PROP. SANITARY SEWER
- PROP. CLEANOUT



The underground utilities shown have been located from field survey information and existing records. The surveyor makes no guarantees that the underground utilities shown comprise all such utilities in the area, either in-service or abandoned. The surveyor further does not warrant that the underground utilities shown are in the exact location indicated. Although the surveyor does certify that they are located as accurately as possible from the information available.


| | |
|-------------|------------------|
| JOB No. | 20213 |
| ISSUED: | CITY SUBMITTAL 1 |
| REV. DATE | 06-07-21 |
| REV. DATE | 07-09-21 |
| DATE: | 7/7/2021 |
| SHEET | 14 |
| OF | 25 |
| CADD: | JAM |
| ENG.: | JAM |
| PM: | RCW |
| TECH: | RCW |
| 2021302.dwg | |

MA:\CIVIL\3D_Plan\2021\3D\Detail\Eng\2021\3D\03.dwg, 7/9/2021 4:51 PM, Jeremy A. Matthei, C3.2 WATER LEAD PLAN & PROFILE.MDL, L.L.C. PDF, p.03
Copyright © 2021, Midwestern Consulting L.L.C. All rights reserved. No part of this drawing may be used or reproduced in any form or by any means, or stored in a database or retrieval system, without prior permission of Midwestern Consulting L.L.C.



LEGEND

| | | |
|-------|-------|------------------------------|
| --- | 772 | EXIST. CONTOUR |
| --- | 772 | PROP. CONTOUR |
| ○ | U.P. | EXIST. UTILITY POLE |
| — | OH | GUY WIRE |
| — | OH | EXIST. OVERHEAD UTILITY LINE |
| * | * | EXIST. LIGHT POLE |
| g | g | EXIST. GAS LINE |
| w | w | EXIST. WATER MAIN |
| h | h | EXIST. HYDRANT |
| r | r | EXIST. GATE VALVE IN BOX |
| □ | □ | EXIST. STORM SEWER |
| □ | □ | EXIST. CATCH BASIN OR INLET |
| - - - | - - - | EXIST. SANITARY SEWER |
| p | p | SIGN |
| g | g | GAS METER |
| • | • | POST |
| — | — | FENCE |
| • | • | SINGLE TREE |
| ☁ | ☁ | TREE OR BRUSH LIMIT |
| ⊕ | TP-1 | EXIST. TEST PIT LOCATION |
| △ | △ | CONTROL PT. |
| T | T | PROP. TELEPHONE LINE |
| E | E | PROP. ELECTRIC LINE |
| R | R | PROP. STORM SEWER |
| □ | □ | PROP. CATCH BASIN OR INLET |
| W | W | PROP. WATER MAIN |
| S | S | PROP. SANITARY SEWER |
| ○ | ○ | PROP. CLEANOUT |



The underground utilities shown have been located from field survey information and existing records. The surveyor makes no guarantees that the underground utilities shown comprise all such utilities in the area, either in-service or abandoned. The surveyor further does not warrant that the underground utilities shown are in the exact location indicated. Although the surveyor does certify that they are located as accurately as possible from the information available.

| | |
|---|--|
| MIDWESTERN CONSULTING 3845 Plaza Drive Ann Arbor, Michigan 48108 (734) 995-0200 • www.midwesternconsulting.com Land Development • Land Survey • Institutional • Municipal Wireless Communications • Transportation • Landfill Services | |
| CLIENT RACQUET CLUB OF ANN ARBOR 3010 HICKORY LANE ANN ARBOR, MI 48104 BRENT SCHOMAKER 734-216-0579 | |
| JOB No. 20213 ISSUED: CITY SUBMITTAL 1 DATE: 7/7/2021 SHEET 15 OF 25 REV. DATE: 06-07-21 REV. DATE: 07-09-21 CADD: JBB ENG: JAM PM: RCW TECH: RCW 202130P3.dwg | |
| RACQUET CLUB OF ANN ARBOR PUMP HOUSE & SITE RENOVATION SITE PLAN ADMINISTRATIVE AMENDMENT WATER LEAD PLAN & PROFILE | |
| C3.2 | |

M:\Civ\134_P\0213\Detail\Eng\2021\3072.dwg, 7/9/2021 4:51 PM, Jeremy A. Matthei, C3.3 UTILITY DETAILS, MCLC PDF, .p3
 Copyright © 2021, Midwestern Consulting L.L.C. All rights reserved. No part of this drawing may be used or reproduced in any form or by any means, without prior permission of Midwestern Consulting L.L.C.

**Estimated Net Annual Solids Load Reduction
Based on the Rational Rainfall Method**


Racquet Club of Ann Arbor
 Ann Arbor, MI
 WQU

CDS MODEL: 2015-4
 PARTICLE SIZE (µm): 110

| Rainfall Intensity (in/hr) | Percent Rainfall Volume ¹ | Cumulative Rainfall Volume | Total Flowrate (cfs) | Removal Efficiency (%) | Incremental Removal (%) |
|----------------------------|--------------------------------------|----------------------------|----------------------|------------------------|-------------------------|
| 0.02 | 13.13% | 13.1% | 0.02 | 100.00 | 13.13 |
| 0.04 | 11.36% | 24.5% | 0.04 | 100.00 | 11.36 |
| 0.06 | 10.08% | 34.6% | 0.06 | 99.33 | 10.01 |
| 0.08 | 7.49% | 42.1% | 0.08 | 98.65 | 7.39 |
| 0.10 | 7.01% | 49.1% | 0.10 | 97.97 | 6.87 |
| 0.12 | 5.37% | 54.4% | 0.12 | 97.29 | 5.22 |
| 0.14 | 4.73% | 59.2% | 0.14 | 96.61 | 4.57 |
| 0.16 | 4.13% | 63.3% | 0.16 | 95.92 | 3.96 |
| 0.18 | 3.53% | 66.8% | 0.18 | 95.24 | 3.36 |
| 0.20 | 2.99% | 69.8% | 0.20 | 94.56 | 2.83 |
| 0.25 | 5.50% | 75.3% | 0.25 | 92.85 | 5.11 |
| 0.30 | 4.47% | 79.8% | 0.30 | 91.15 | 4.07 |
| 0.35 | 3.85% | 83.6% | 0.35 | 89.44 | 3.44 |
| 0.40 | 2.16% | 85.8% | 0.40 | 87.7 | 1.9 |
| 0.45 | 2.09% | 87.9% | 0.45 | 86.0 | 1.8 |
| 0.50 | 1.31% | 89.2% | 0.50 | 84.3 | 1.1 |
| 0.75 | 5.07% | 94.3% | 0.75 | 72.1 | 3.7 |
| 1.00 | 2.58% | 96.9% | 1.01 | 54.1 | 1.4 |
| 1.50 | 2.50% | 99.4% | 1.51 | 36.0 | 0.9 |
| 2.00 | 0.51% | 99.9% | 2.01 | 27.0 | 0.1 |
| 2.54 | 0.15% | 100.0% | 2.55 | 21.3 | 0.0 |
| | | | | | 92.25 |
| | | | | | 97.1% |





Predicted % Annual Rainfall Treated = **97.1%**
 Predicted Net Annual Load Removal Efficiency = **92.2%**

1 - Based on Rainfall Data from DETROIT CITY AP Station



NOTE:
 1) TRENCH DETAILS SHOW TYPE OF BACKFILL AND SURFACE RESTORATION ONLY.
 2) TRENCHING TO CONFORM TO ALL APPLICABLE N.I.O.S.H.A. STANDARDS.
 3) DENSITY TESTING PER CITY SPECIFICATIONS.

TRENCH BACKFILL UNDER PAVEMENT
 (CITY OF ANN ARBOR TRENCH DETAIL 1)
 NO SCALE



CONNECTION DETAIL TO EXISTING RTANK STORM CHAMBER
NO SCALE

Project: Racquet Club of Ann Arbor
Location: Ann Arbor, MI
Prepared For: Midwestern Consulting

Purpose: To calculate the first flush runoff flow rate (WQF) over a given site area. In this situation the WQV to be analyzed is the runoff produced by the first 1" of rainfall.

Reference: United States Department of Agriculture Natural Resources Conservation Service TR-55 Manual

| Structure Name | A (acres) | A (miles ²) | Runoff Coefficient | Percent Imp. (%) | t _c (min) | t _c (hr) |
|----------------|-----------|-------------------------|--------------------|------------------|----------------------|---------------------|
| WQU | 1.50 | 0.00234 | 0.67 | 61.67 | 15.0 | 0.250 |

* Assumes runoff coefficient of 0.3 for pervious areas and 0.9 for impervious areas.

Procedure: The Water Quality Flow (WQF) is calculated using the Water Quality Volume (WQV). This WQV, converted to watershed inches, is substituted for the runoff depth (Q) in the Natural Resources Conservation Service (formerly Soil Conservation Service), TR-55 Gr

1. Compute WQV in watershed inches using the following equation:

$$WQV = P \cdot R$$

where: WQV = water quality volume (watershed inches)
 P = design precipitation (inches)
 R = volumetric runoff coefficient = 0.05 + 0.009(I)
 I = percent impervious cover

| Structure Name | Percent Imp. (%) | R | P | WQV (in) | WQV (CF) |
|----------------|------------------|-------|---|----------|----------|
| WQU | 61.67 | 0.805 | 1 | 0.605 | 3,294.23 |

2. Compute the NRCS Runoff Curve Number (CN) using the following equation, or graphically using Figure 2-1 from TR-55 (USDA, 1986):

$$CN = 1000 / (10 + 5P + 10Q - 10(Q + 1.25Q^2)^{0.5})$$

where: CN = Runoff Curve Number
 P = design precipitation (inches)
 Q = runoff depth (watershed inches)

| Structure Name | Q (in) | CN |
|----------------|--------|-------|
| WQU | 0.605 | 95.64 |

3. Using computed CN, read initial abstraction (I_a) from Table 4-1 in Chapter 4 of TR-55; compute I_a/P, interpolating when appropriate.

| Structure Name | I _a (in) | I _a /P |
|----------------|---------------------|-------------------|
| WQU | 0.083 | 0.083 |

4. Compute the time of concentration (t_c) in hours and the drainage area in square miles. A minimum t_c of 0.167 hours (10 minutes) should be used.

| Structure Name | t _c (hr) | A (miles ²) |
|----------------|---------------------|-------------------------|
| WQU | 0.250 | 0.00234 |

5. Read the unit peak discharge (q_u) from Exhibit 4-II in Chapter 4 of TR-55 for appropriate t_c for type II rainfall distribution.



| Structure Name | t _c (hr) | I _a /P | q _u (csm/in) |
|----------------|---------------------|-------------------|-------------------------|
| WQU | 0.250 | 0.083 | 731 |

6. Substituting WQV (watershed inches) for runoff depth (Q), compute the water quality flow (WQF) from the following equation:

$$WQF = (q_u)(A)(Q)$$

where: WQF = water quality flow (cfs)
 q_u = unit peak discharge (cfs/m²/inch)
 A = drainage area (mi²)
 Q = runoff depth (watershed inches)


| Structure Name | q _u (csm/in) | A (miles ²) | Q (in) | WQF (cfs) |
|----------------|-------------------------|-------------------------|--------|-----------|
| WQU | 731 | 0.00234 | 0.605 | 1.04 |



CDS2015-4-C DESIGN NOTES

THE STANDARD CDS2015-4-C CONFIGURATION IS SHOWN. ALTERNATE CONFIGURATIONS ARE AVAILABLE AND ARE LISTED BELOW. SOME CONFIGURATIONS MAY BE COMBINED TO SUIT SITE REQUIREMENTS.

| CONFIGURATION DESCRIPTION | |
|---|--|
| GRATED INLET ONLY (NO INLET PIPE) | |
| GRATED INLET WITH INLET PIPE OR PIPES | |
| CURB INLET ONLY (NO INLET PIPE) | |
| CURB INLET WITH INLET PIPE OR PIPES | |
| SEPARATE OIL BAFFLE (SINGLE INLET PIPE REQUIRED FOR THIS CONFIGURATION) | |
| SEDIMENT WEIR FOR NUDEP/NUCAT CONFORMING UNITS | |



SITE SPECIFIC DATA REQUIREMENTS

| STRUCTURE ID | WATER QUALITY FLOW RATE (CFS OR L/s) | PEAK FLOW RATE (CFS OR L/s) | RETURN PERIOD OF PEAK FLOW (YRS) | SCREEN APERTURE (2400 OR 4700) |
|--------------|--------------------------------------|-----------------------------|----------------------------------|--------------------------------|
| | * | * | * | * |

| PIPE DATA | I.E. | MATERIAL | DIAMETER |
|--------------|------|----------|----------|
| INLET PIPE 1 | * | * | * |
| INLET PIPE 2 | * | * | * |
| OUTLET PIPE | * | * | * |

| RIM ELEVATION | ANTI-FLOTATION BALLAST | WIDTH | HEIGHT |
|---------------|------------------------|-------|--------|
| * | * | * | * |

NOTES/SPECIAL REQUIREMENTS:
 * PER ENGINEER OF RECORD

GENERAL NOTES:
 1. CONTECH TO PROVIDE ALL MATERIALS UNLESS NOTED OTHERWISE.
 2. DIMENSIONS MARKED WITH () ARE REFERENCE DIMENSIONS. ACTUAL DIMENSIONS MAY VARY.
 3. FOR FABRICATION DRAWINGS WITH DETAIL STRUCTURE DIMENSIONS AND WEIGHTS, PLEASE CONTACT YOUR CONTECH ENGINEERED SOLUTIONS LLC REPRESENTATIVE. www.contechES.com
 4. CDS WATER QUALITY STRUCTURE SHALL BE IN ACCORDANCE WITH ALL DESIGN DATA AND INFORMATION CONTAINED IN THIS DRAWING.
 5. STRUCTURE SHALL MEET AASHTO H20 AND CASTINGS SHALL MEET H20 (AASHTO M 300) LOAD RATING, ASSUMING GROUNDWATER ELEVATION AT OR BELOW THE OUTLET PIPE INVERT ELEVATION. ENGINEER OF RECORD TO CONFIRM ACTUAL GROUNDWATER ELEVATION.
 6. PVC HYDRAULIC BREAK PLATE IS PLACED ON SHELF AT BOTTOM OF SCREEN CYLINDER. REMOVE AND REPLACE AS NECESSARY DURING MAINTENANCE CLEANING.
 INSTALLATION NOTES:
 A. ANY SUB-BASE BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE-SPECIFIC DESIGN CONSIDERATIONS AND SHALL BE SPECIFIED BY ENGINEER OF RECORD.
 B. CONTRACTOR TO PROVIDE EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE CDS MANHOLE STRUCTURE (LIFTING CLUTCHES PROVIDED).
 C. CONTRACTOR TO ADD JOINT SEALANT BETWEEN ALL STRUCTURE SECTIONS, AND ASSEMBLE STRUCTURE.
 D. CONTRACTOR TO PROVIDE, INSTALL, AND GROUT PIPES. MATCH PIPE INVERTS WITH ELEVATIONS SHOWN.
 E. CONTRACTOR TO TAKE APPROPRIATE MEASURES TO ASSURE UNIT IS WATER TIGHT, HOLDING WATER TO FLOWLINE INVERT MINIMUM. IT IS SUGGESTED THAT ALL JOINTS BELOW PIPE INVERTS ARE GROUTED.

CONTECH ENGINEERED SOLUTIONS LLC
 8025 Centre Pointe Dr., Suite 400, West Chester, OH 45399
 503-338-1122 513-645-7000 513-645-7993 FAX

CDS2015-4-C
 INLINE CDS
 STANDARD DETAIL

MIDWESTERN CONSULTING
 3815 Plaza Drive Ann Arbor, Michigan 48108
 (734) 995-0200 • www.midwesternconsulting.com
 Land Development • Land Survey • Institutional • Municipal
 Wireless Communications • Transportation • Landfill Services

CLIENT
 RACQUET CLUB OF ANN ARBOR
 3010 HICKORY LANE
 ANN ARBOR, MI 48104
 BRENT SCHOMAKER
 734-216-0579




UTILITY DETAILS
 PUMP HOUSE & SITE RENOVATION
 SITE PLAN ADMINISTRATIVE AMENDMENT

C3.3

| DATE | REV. | DATE | REV. |
|----------|------|----------|------|
| 7/7/2021 | 16 | 06-07-21 | 1 |

JOB No. **20213**
 ISSUED: **06-07-21**
 CITY SUBMITTAL 1
 CITY SUBMITTAL 2
 TECH: RCW
 20213012.dwg

Midwestern Consulting L.L.C. 3815 Plaza Drive Ann Arbor, Michigan 48108 (734) 995-0200 • www.midwesternconsulting.com Land Development • Land Survey • Institutional • Municipal Wireless Communications • Transportation • Landfill Services



LEGEND

- 772 EXIST. CONTOUR
- 772 PROP. CONTOUR
- SIGN
- POST
- FENCE
- SINGLE TREE
- TREE OR BRUSH LIMIT
- EXIST. STORM SEWER
- PROP. STORM SEWER
- EXIST. CATCH BASIN OR INLET
- PROP. CATCH BASIN OR INLET

Racquet Club - Pump House & Site Renovation
Midwestern Consulting Project # 20213
5/26/2021

Rational C Values:

| Soil Type | Roof/Pvmt. | Vegetated | Water |
|-----------|------------|-----------|-------|
| A | 0.95 | 0.20 | 1.00 |
| B | 0.95 | 0.30 | 1.00 |
| C | 0.95 | 0.35 | 1.00 |
| D | 0.95 | 0.50 | 1.00 |

The NRCS Soils Report indicates BnB - Boyer Loamy Sand throughout the project site, with Hydrologic Group B. However excellent sandy soils were found in the soils investigation near the work zone, so Soil Type A is used, as in the 2016 project at the same site.

| Inlet/Area # | sft total area | sft roof | sft pvmt. | sft water | total imp. | sft veg. | Soil Type | Veg C | CxA (sft) | CxA (ac) | Area (ac) | C Value |
|------------------------------------|----------------|--------------|---------------|-----------|---------------|---------------|-----------|-------------|---------------|--------------|--------------|-------------|
| R-1 (Storm Tank) | 0 | 0 | 0 | 0 | 0 | 0 | A | 0.20 | 0 | 0.000 | 0.000 | 0.00 |
| R-2 (Water Quality Manhole) | 0 | 0 | 0 | 0 | 0 | 0 | A | 0.20 | 0 | 0.000 | 0.000 | 0.00 |
| R-3 (Curb Inlet) | 2,152 | 0 | 1,310 | 0 | 1,310 | 842 | A | 0.20 | 1,413 | 0.032 | 0.049 | 0.66 |
| R-4 (Perimeter Trench Drain) | 16,894 | 0 | 14,354 | 0 | 14,354 | 2,540 | A | 0.20 | 14,144 | 0.325 | 0.388 | 0.84 |
| R-5 (Cleanout) | 0 | 0 | 0 | 0 | 0 | 0 | A | 0.20 | 0 | 0.000 | 0.000 | 0.00 |
| R-6 (Pump House Roof) | 1,069 | 1,069 | 0 | 0 | 1,069 | 0 | A | 0.20 | 1,016 | 0.023 | 0.025 | 0.95 |
| R-7 (Bio-Infiltration Rain Garden) | 935 | 0 | 825 | 0 | 825 | 110 | A | 0.20 | 806 | 0.018 | 0.021 | 0.86 |
| 2016 Project Areas "A+C" | 44,237 | 8,695 | 16,517 | 0 | 25,212 | 19,025 | A | 0.20 | 27,756 | 0.637 | 1.016 | 0.63 |
| TOTAL AREAS TO STORM TANKS | 65,287 | 9,764 | 33,006 | 0 | 42,770 | 22,517 | A | 0.20 | 45,135 | 1.036 | 1.499 | 0.69 |

CLIENT
RACQUET CLUB OF ANN ARBOR
3010 HICKORY LANE
ANN ARBOR, MI 48104
BRENT SCHOMAKER
734-216-0579

JOB No. 20213

DATE: 7/7/2021
SHEET: 18 OF 25
REV. DATE: 06-07-21
CADD: JBB
ENG.: JAM
DATE: 07-09-21
PM: RCW
TECH: RCW
20213SWT.dwg

The underground utilities shown have been located from field survey information and existing records. The surveyor makes no guarantees that the underground utilities shown comprise all such utilities in the area, either in-service or abandoned. The surveyor further does not warrant that the underground utilities shown are in the exact location indicated. Although the surveyor does certify that they are located as accurately as possible from the information available.

MIDWESTERN CONSULTING
3815 Plaza Drive Ann Arbor, Michigan 48108
(734) 995-0200 • www.midwesternconsulting.com
Land Development • Land Survey • Institutional • Municipal
Wireless Communications • Transportation • Landfill Services

RACQUET CLUB OF ANN ARBOR
PUMP HOUSE & SITE RENOVATION
SITE PLAN ADMINISTRATIVE AMENDMENT
STORMWATER PLAN

C4.0

Underground Tank Stormwater Calculations

REV 5/26/2021

W1 - Determining Post-Development Cover Types, Areas, Curve Numbers, and Runoff Coefficients

Table with 5 columns: Cover Type, Soil Type, Area (sqft), Area (ac), Runoff Coeff. (C), (C) x (Area). Rows include Building, Pavement, Grass (A, B, C, D), Water Surface, and Total.

Table with 5 columns: Cover Type, Soil Type, Area (sqft), Area (ac), Curve Number, (CN) x (Area). Rows include Grass (A, B, C, D), Water Surface, and Total.

Table with 5 columns: Cover Type, Soil Type, Area (sqft), Area (ac), Curve Number, (CN) x (Area). Rows include Building, Pavement, Water Surface, and Total.

W2 - W2 - First Flush Runoff Calculations (Vff)
A. Vff = 1" x 17/12" x 43560 sqft/ac x A x C where A= 1.50 and where C= 0.67
Vff = 1" x 17/12" x 43560 sqft/ac x 1.50 x 0.67 = 3,645 cft

W3 - W3 - Pre-Development Bankfull Runoff Calculations (Vbf-pre)
A. 2 year / 24 hour storm event: P= 2.35 in
B. Pre-Development CN (Good Cover Woods, Type A Soils) CN= 30
C. S = (1000 / CN) - 10 S= 23,333 in
D. Q = [(P-0.2S)^2] / [P+0.8S] Q= 0.000 in
E. Total Site Area excluding "Self-Crediting" BMPs 65,287 sqft
F. Vbf-pre = Q x (1/12) x Area Vbf-pre = 0 cft

W4 - W4 - Pervious Cover Post-Development Bankfull Runoff Calculations (Vbf-per-post)
A. 2 year / 24 hour storm event: P= 2.35 in
B. Pervious Cover CN From Worksheet 1 CN= 49
C. S = (1000 / CN) - 10 S= 10,408 in
D. Q = [(P-0.2S)^2] / [P+0.8S] Q= 0.007 in
E. Pervious Cover Area from Worksheet 1 22,517 sqft
F. Vbf-per-post = Q x (1/12) x Area Vbf-per-post = 13 cft

W5 - W5 - Impervious Cover Post-Development Bankfull Runoff Calculations (Vbf-imp-post)
A. 2 year / 24 hour storm event: P= 2.35 in
B. Impervious Cover CN From Worksheet 1 CN= 98
C. S = (1000 / CN) - 10 S= 0.204 in
D. Q = [(P-0.2S)^2] / [P+0.8S] Q= 2,122 in
E. Impervious Cover Area from Worksheet 1 42,770 sqft
F. Vbf-imp-post = Q x (1/12) x Area Vbf-imp-post = 7,562 cft

W6 - W6 - Pervious Cover Post-Development 100-Year Runoff Calculations (V100-per-post)
A. 100 year / 24 hour storm event: P= 5.11 in
B. Pervious Cover CN From Worksheet 1 CN= 49
C. S = (1000 / CN) - 10 S= 10,408 in
D. Q = [(P-0.2S)^2] / [P+0.8S] Q= 0.683 in
E. Pervious Cover Area from Worksheet 1 22,517 sqft
F. V100-per-post = Q x (1/12) x Area V100-per-post = 1,281 cft

W7 - W7 - Impervious Cover Post-Development 100-Year Runoff Calculations (V100-imp-post)
A. 2 year / 24 hour storm event: P= 5.11 in
B. Impervious Cover CN From Worksheet 1 CN= 98
C. S = (1000 / CN) - 10 S= 0.204 in
D. Q = [(P-0.2S)^2] / [P+0.8S] Q= 4,873 in
E. Impervious Cover Area from Worksheet 1 42,770 sqft
F. Vbf-imp-post = Q x (1/12) x Area Vbf-imp-post = 17,368 cft

W8 - Time of Concentration (Tc-hrs)
A. Assume 15-minute minimum time of concentration Tc= 0.25 hr

W9 - Runoff Summary & On-Site Infiltration Requirement
A. Summary from Previous Worksheets
First Flush Volume (Vff) 3,645 cft
Pre-Development Bankfull Runoff Volume (Vbf-pre) 0 cft
Pervious Cover Post-Development Bankfull Volume (Vbf-per-post) 13 cft
Impervious Cover Post-Development Bankfull Volume (Vbf-imp-post) 7,562 cft
Total BF Volume (Vbf-post) 7,575 cft
Pervious Cover Post-Development 100-Year Volume (V100-per-post) 1,281 cft
Impervious Cover Post-Development 100-Year Volume (V100-imp-post) 17,368 cft
Total 100-Year Volume (V100) 18,649 cft
B. Determine Onsite Infiltration Requirement
Subtract the Pre-Development Bankfull from the Post-Development Bankfull Volume
Total Post-Development Bankfull Volume (Vbf-post) 7,575 cft
Pre-Development Bankfull Runoff Volume (Vbf-pre) 0 cft
Bankfull Volume Difference 7,575 cft
Infiltration Requirement (Vin) 7,575 cft

W10 - Detention/Retention Requirement
A. Qp = 238.6 Tc^0.82 743.63 cfs/(in x sq. mi)
B. Total Site Area excluding "Self-Crediting" BMPs 1.50 ac
C. Q100 = Q100-per + Q100-imp 5,556 in
D. Peak Flow (PF) = Qp x Q100 x Area / 640 9.67 cfs
E. Delta = PF - 0.15 x Area (ac) 9.45 cfs
F. Vdet = Delta / PF x V100 0.22 cfs
Required Detention not including infiltration credit or penalty. 18,216 cft
Sediment Forebay Volume Required (5% of V100) 932 cft

Table with 5 columns: Proposed BMP, Area (sqft), Storage Volume (cft) Surface, In Soil, Design Infil. Rate (in/hr), Infil. Volume in 6-hr Drawdown (cft), Total Volume Reduction (cft). Rows include Pervious Pavement, Infiltration Bed, Subsurface Infiltration Bed (RTank), Infiltration Trench, Bioretention Systems, Rain Gardens, Dry Well, Bioswale, Vegetated Filter Strip, Green Roof.

W12 - Natural Features Inventory
There are no natural features located on this site due to it being an existing built out urban site. Refer to Sheet C1.1 for location and size of natural features.

W13 - Site Summary of Infiltration & Detention
A. Stormwater Management Summary
Min infiltration Requirement (Vinf) 7,575 cft
Designed/Provided Infiltration Volume 24,416 cft
% Minimum Required Infiltration Provided 322 %
Total Calculated Detention Volume, Vdet 18,216 cft
Net Required Detention Volume (Vdet - Designed/Provided Infiltration Volume) -6,200 cft
B. Detention Volume Increase for sites where the required infiltration volume cannot be achieved.
% Required Infiltration NOT Provided 0.0 %
(100% - % Minimum Required Infiltration Provided)
Net % Penalty (20% x % Required Infiltration NOT Provided) 0.0 %
Total Required Detention Volume, including penalty (6,200) cft
[(100% + Net % Penalty) x Net Required Detention Volume]

Table with 5 columns: Storm Event, Req'd Volume, less Infil. Credit, Final Volume. Rows include First Flush, Bankfull, 100-year, Forebay Volume Required (5% of 100-yr).

Table with 5 columns: Elevation, Area (sqft), Depth (ft), Volume (cft)*, Cum. Volume (cft). Rows show elevation from 763.0 to 769.5.

Storage Elevation Calculation
First Flush Elevation (Xff)= 764.0 - 763.0 = Xff - 763.0 Xff = 763.00 ft
Bankfull Elevation (Xbf)= 764.0 - 763.0 = Xbf - 763.0 Xbf = 763.00 ft
100-Year Elevation (X100)= 765.0 - 764.0 = X100 - 764.0 X100 = 764.62 ft

C. Full Infiltration Design
Total Storage Volume 4,216 cft
Infiltration Area 2800 sqft
Infiltration Rate, Average 10.00 in/hr
Infiltration Flow Rate 2333.33 cft/hr
Time to Fully Drain 1.8 hr
This is less than 48 hours max, so the basin complies with the drawdown requirement.

Racquet Club of Ann Arbor - Pump House and Site Renovation
May 26, 2021

Stormwater Narrative:

This redevelopment project follows the 2016 WCWRC design criteria.
Less than 50% of the site is disturbed, so existing, undisturbed areas continue to drain in their current condition. Since the total site contains more than 10,000 sqft of impervious surface area, the 100-year storm will be detained, for the disturbed area. Test pits performed in 2015 indicated excellent infiltration in sandy soils, with a recorded rate of 27.75 inches/hour. The Factor of Safety of 2 gives 13.8 inches/hour, which is greater than the statutory 10.0 inches per hour used in this calculation.


A underground storm chamber infiltration system was installed in the 2016 construction project, and was designed very conservatively to store the full storm volume without any allowance for infiltration to reduce the tank volumes. As a result of this, and based on anecdotal observation that standing water has never been seen in this system, we are using this spare capacity allowed for in the City and County regulations to detain and infiltrate the newly disturbed site areas within the existing RTank system.

Water quality treatment for the first flush storm will be provided by a new underground hydrodynamic separator that will handle the flow from the newly disturbed area, into the chambers. These chambers will also receive the pool backwash and drainage water that is being rerouted from the sanitary sewer as a result of this project, and treated per EGLE regulations.


In case of a failure of the infiltration bed or a storm exceeding the 100-year design storm, an overflow outlet for the storm chambers was installed in 2016 with an invert at the height of the infiltration top of tank.

Outlet Certification:
Based upon the data and criteria outlined above, I hereby certify that the existing drain is the only reasonably achievable stormwater outlet for the proposed stormwater management system, and that the existing drain has sufficient capacity to serve as an adequate outlet for the proposed system, without detriment to or diminution of the drainage serve that the existing outlet presently provides.

Signed: Jeremy Matthei
Jeremy Matthei, PE #62010 53590



MIDWESTERN CONSULTING
3815 Plaza Drive Ann Arbor, Michigan 48108
(734) 995-0200 • www.midwesternconsulting.com
Land Development • Land Survey • Institutional • Municipal
Wireless Communications • Transportation • Landfill Services



CLIENT
RACQUET CLUB OF ANN ARBOR
3010 HICKORY LANE
ANN ARBOR, MI 48104
BRENT SCHOMAKER
734-216-0579

RACQUET CLUB OF ANN ARBOR
PUMP HOUSE & SITE RENOVATION
SITE PLAN ADMINISTRATIVE AMENDMENT
STORM CALCULATIONS

C4.1

20213
DATE: 7/7/2021
SHEET 19 OF 25
REV. DATE: 06-07-21
CADD: JBB
ENG: JAM
PM: RCW
TECH: RCW
20213SN2.dwg

STORM PIPE CALCULATION SHEET
Racquet Club - Pump House & Site Renovation - 20213 - 5/26/2021

Table with columns: Structure No., Drainage Area, Runoff Coeff., CxA, ADD, CxA, Time T, Rainfall, Q, Q Inlet Here, Pipe Dia., Length, Slope, Velocity, Travel Time, Sewer Capacity, Spare Capacity, Invert, Rim, Cover, H.G. Slope, Down stream HGL, Up stream HGL, Down stream HGL, Up stream HGL. Rows include R-2, R-3, R-4, R-5.

The underground utilities shown have been located from field survey information and existing records. The surveyor makes no guarantees that the underground utilities shown comprise all such utilities in the area, either in-service or abandoned. The surveyor further does not warrant that the underground utilities shown are in the exact location indicated. Although the surveyor does certify that they are located as accurately as possible from the information available.

Midwestern Consulting L.L.C. All rights reserved. No part of this drawing may be used or reproduced in any form or by any means, or stored in a database or retrieval system, without prior permission of Midwestern Consulting L.L.C.

Stormwater Narrative
Racquet Club of Ann Arbor
August 13, 2015

Ordinance: This project is bound by the Washtenaw County Water Resources Commissioner Rules and Guidelines, Issued August 6, 2014. The regulations require that the greater of the 1-inch storm volume or the increase in the 2-year storm volume be infiltrated, if feasible, and that the 100-year storm runoff be reduced to less than 0.15 cfs/acre. If infiltration is infeasible, an additional 20% penalty is applied to the storage volume required. Additionally, the 1-inch storm must be treated for water quality to remove 80% of total suspended solids.

Portion of Site Modified: If less than 50% of a site is being modified, the portion modified must be fully brought up to standards, and the remainder of the site must be treated for quality. If more than 50% of a site is modified, the full site must be brought up to current standards. This site will be 11.4% modified (0.88 of 7.72 acres), so the modified portion will be infiltrated, with the remainder treated for quality.

General Approach: The site consists of BnB Boyer Loamy Sands, a Type A well-draining soil. However due to current basement flooding issues near the buildings, the project will take the storm water to the north end of the site, near Test Pit 1. Due to the very well draining soils, the project will infiltrate the entire 100-year storm event in less than 48 hours, with the only outlet pipe from the infiltration chambers being an emergency overflow pipe to the existing storm line.

Infiltration Rate: The infiltration test results from Test Pit 1 indicated a 27.75 in/hour infiltration rate. The WCWRC requires a minimum factor of safety of 2, and we are using a factor of safety of 9.25, to obtain a conservative design infiltration rate of 3.00 in/hr. With this rate the full 4' high chambers can infiltrate the 100-year storm in 14.5 hours, well under the 2-year storm infiltration goal of 48 hours.

Outlet Path: Presently, most of the paved portions of the site drain through catch basins into a 6-inch storm pipe running from south to north on the site, before tying into the City storm sewer on Huron River Drive. While this pipe is undersized based upon modern design standards, the facility has not faced surface ponding issues due to the generally well-draining soils and the well-established overland flow paths throughout the site. Additionally, portions of the site sheet-flow to the east, south, and north across vegetated surfaces, partially infiltrating into the ground, with the remainder eventually reaching the City's storm sewers in the adjacent roadways.

Infiltration Chamber Design: Due to a desire to preserve landscaping and reduce construction impacts, the infiltration system will be placed underground in chambers, near Test Pit 1. To further reduce site impacts, RTank (or engineer-approved equal) chambers with 93% voids will be used, and the pre-treatment and emergency outlet control will invert at the top of the chamber elevation will also be underground. They are sized to handle the full 100-year storm volume of the disturbed site area, and our calculations indicate that due to infiltration out of the chambers during the storm events, the tank will not overflow when handling the larger stormwater volume routed to them in a 100-year event.


Water Quality Design: Before entering the infiltration chamber, the stormwater will pass through a hydrodynamic separator (Contech CDS or approved equal) sized to handle the pipe capacity leading to it. The hydrodynamic separator will treat the 10-year design storm flow rate (2.6 cfs) to at least the 90% TSS standard, and any remaining solids will be filtered in the soils beneath the infiltration chamber.

Conveyance Systems: New Pipes and swales are designed to convey the 10-year storm without surcharging above the crown of pipe, flowing full, following the calculation methodology in the WCWRC Rules and Guidelines.

Free Release Areas: Certain small areas (0.28 acres) along the edge of the site free-release to the east, west, north, and south, and to the pool, as collecting the water from these areas is difficult. However they are mitigated by taking in 0.41 acres of undisturbed site runoff at Structure R-37 and R-45. Calculations of the "disturbed area runoff" and of the "infiltrated area runoff" were undertaken to ensure that the stormwater requirements would be exceeded. The project intends to use this trade-off of areas to comply with the regulations.

LEGEND:

- LIMITS OF DISTURBANCE MAIN SITE WORK
- LIMITS OF DISTURBANCE HICKORY LANE SIDEWALK WORK (EXEMPT FROM STORMWATER MANAGEMENT REQUIREMENTS)
- - - BREAK LINE BETWEEN DETAINED AND FREE RELEASE
- - - WATERSHED BOUNDARY FOR CHAMBERS
- - - SUB-WATERSHED BOUNDARY FOR INLET DRAINAGE AREAS
- 42 INLET & SUB-WATERSHED NUMBER
- ▨ ROOF AREA
- ▩ PAVEMENT AREA
- ▨ PERMEABLE PAVEMENT AREA
- ▨ OFFSITE PAVEMENT AREA DRAINING TO CHAMBERS



DISTURBED SITE AREA*: 0.88 AC
TOTAL SITE AREA**: 7.72 AC
PORTION OF SITE DISTURBED: 11.4%
50% DISTURBANCE FOR FULL-SITE STORMWATER CONTROL NOT TRIGGERED.
*EXCLUDES PUBLIC SIDEWALK CONSTRUCTION AREA OF 0.15 AC.
**EXCLUDES EXISTING AND PROPOSED ROADWAY RIGHT-OF-WAY.

TOTAL DISTURBED PROJECT AREA INCLUDING PUBLIC SIDEWALK: 1.03 AC

MIDWESTERN CONSULTING
Civil, Environmental and Transportation Engineers
Planners, Surveyors
Landscape Architects
3815 Plaza Drive
Ann Arbor, Michigan 48108
Phone: 734.995.0200
Fax: 734.995.0589

MIDWESTERN CONSULTING
3815 Plaza Drive Ann Arbor, Michigan 48108
(734) 995-0200 • www.midwesternconsulting.com
Land Development • Land Survey • Institutional • Municipal
Wireless Communications • Transportation • Landfill Services

CLIENT
RACQUET CLUB OF ANN ARBOR
3010 HICKORY LANE
ANN ARBOR, MI 48104
BRENT SCHOMAKER
(734) 218-0579

RACQUET CLUB OF ANN ARBOR
SITE PLAN
STORMWATER MANAGEMENT PLAN

C8.0

14058

| DATE | REV. | BY | DESCRIPTION |
|------------|------|-----|-------------------------|
| 04/29/2016 | 1 | JAM | ISSUED FOR CONSTRUCTION |

C4.2



20213

| DATE | REV. | BY | DESCRIPTION |
|----------|------|-----|-------------------------|
| 06-07-21 | 1 | JAM | ISSUED FOR CONSTRUCTION |
| 07-09-21 | 2 | JAM | CITY SUBMITTAL |

The underground utilities shown have been located from field survey information and existing records.

The underground utilities shown have been located from field survey information and existing records. The surveyor makes no guarantees that the underground utilities shown comprise all such utilities in the area, either in-service or abandoned. The surveyor further does not warrant that the underground utilities shown are in the exact location indicated. Although the surveyor does certify that they are located as accurately as possible from the information available.

M:\CIVIL\2021\20210301\20210301.dwg, 7/9/2021 4:53 PM, Jeremy A. Matthei, C5.0 SOIL EROSION CONTROL PLAN, MLLC PDF.p03
Copyright © 2021, Midwestern Consulting L.L.C. All rights reserved. No part of this drawing may be used or reproduced in any form or by any means, or stored in a database or retrieval system, without prior permission of Midwestern Consulting L.L.C.



SCALE: 1" = 20'
0 20 40 60



- LEGEND**
- 772 --- EXIST. CONTOUR
 - 772 --- PROP. CONTOUR
 - o- U.P. EXIST. UTILITY POLE
 - - - GUY WIRE
 - OH EXIST. OVERHEAD UTILITY LINE
 - * EXIST. LIGHT POLE
 - EXIST. STORM SEWER
 - PROP. STORM SEWER
 - EXIST. CATCH BASIN OR INLET
 - PROP. CATCH BASIN OR INLET
 - POST SIGN
 - FENCE
 - SINGLE TREE
 - TREE OR BRUSH LIMIT
 - SILT FENCE
 - INLET FILTER BAG

The underground utilities shown have been located from field survey information and existing records. The surveyor makes no guarantees that the underground utilities shown comprise all such utilities in the area, either in-service or abandoned. The surveyor further does not warrant that the underground utilities shown are in the exact location indicated. Although the surveyor does certify that they are located as accurately as possible from the information available.

7.72 ACRES

MIDWESTERN CONSULTING
3835 Plaza Drive Ann Arbor, Michigan 48108
(734) 995-0200 • www.midwesternconsulting.com
Land Development • Land Survey • Institutional • Municipal
Wireless Communications • Transportation • Landfill Services

MIDWESTERN CONSULTING

CLIENT
RACQUET CLUB OF ANN ARBOR
3010 HICKORY LANE
ANN ARBOR, MI 48104
BRENT SCHOMAKER
734-216-0579

RACQUET CLUB OF ANN ARBOR
PUMP HOUSE & SITE RENOVATION
SITE PLAN ADMINISTRATIVE AMENDMENT
SOIL EROSION CONTROL PLAN

C5.0

| | |
|--------------|------------------|
| JOB No. | 20213 |
| ISSUED: | CITY SUBMITTAL 1 |
| REV. DATE: | 06-07-21 |
| REV. DATE: | 07-09-21 |
| DATE: | 7/7/2021 |
| SHEET 22 | OF 25 |
| CADD: | JB |
| ENG.: | JCM |
| TECH.: | RCW |
| 20213SE1.dwg | |

M:\CIVIL\134_P\134_P\134_P\2021\3UR1.dwg, 7/9/2021 2:07 PM, Jeremy A. Matthei, L1.0 OVERALL LANDSCAPE PLAN, MLLC PDF ps3
 Copyright © 2021, Midwestern Consulting L.L.C. All rights reserved. No part of this drawing may be used or reproduced in any form or by any means, or stored in a database or retrieval system, without prior permission of Midwestern Consulting L.L.C.

DEVONSHIRE (60' WD.)



LANDSCAPE LEGEND

- PROPOSED CANOPY TREE (STREET TREE)
- PROPOSED DECIDUOUS SHRUBS (RIGHT OF WAY SCREENING)
- PROPOSED EVERGREEN SHRUBS (RIGHT OF WAY SCREENING)
- EXISTING TREE TO REMAIN
- PROPOSED LAWN AREA
- PROPOSED LANDSCAPE BED AND MULCH
- EXISTING VEHICULAR USE AREA - BIO-RETENTION
- EXISTING VEHICULAR USE AREA
- VEHICULAR USE AREA LIMITS

LANDSCAPE REQUIREMENTS

| | Required | Proposed |
|---|--|---|
| Right-of-way screening | 10ft when VUA viewed from ROW 1 tree per 30ft; continuous hedge/screen | Hickory Lane - Not applicable Geddes - 14 existing trees to remain, 22 shrubs proposed |
| Vehicle Use Area | | |
| Interior islands | 1:20sf ratio for island, 23,711sf / 20 = 1,186sf island | 9,546sf existing |
| Bio-retention island | if >750sf island; 50% bioretention 1,186sf / 2 = 593sf bioretention island | 1,401sf existing bio-retention |
| Interior island trees | 1 tree per island; 1 tree per 250sf island; 1,186sf / 250 = 5 trees | 13 existing trees to remain |
| Snow pile storage | identify locations on plan | shown on plans |
| Street Trees | | |
| Street trees | 1 tree per 45lf Hickory Lane - 813lf / 45 = 18 trees Geddes Road - 316lf / 45 = 7 trees Huron Parkway - 683lf / 45 = 16 trees | Hickory Lane - 18 trees proposed Geddes Road - 7 trees proposed Huron Parkway - 2 existing, 13 trees proposed |
| Street tree escrow | \$1.30 per linear foot frontage Hickory Lane - 813lf x \$1.30 = \$1056.90 Geddes Road - 316lf x \$1.30 = \$410.80 Huron Parkway - 683lf Huron Parkway Credit for 2 existing trees: 45 x 2 trees = 90LF. Net Huron Parkway - 683LF - 90LF = 593LF 593LF x \$1.30 = \$770.90 Total: \$1,056.90 + \$410.80 + \$770.90 = \$2,238.60 | \$2,238.60 to City Tree Fund prior to issuing building permits.* |
| Street tree canopy loss fee | Not applicable | Not applicable |
| Conflicting Land Use Buffer | VUA screening when adjacent to public park or residential purposes | Not applicable; VUA not adjacent to residentially zoned parcels |
| Tree Mitigation | 50% DBH of Woodland and LM | Not Applicable |
| Outdoor refuse | screening required from adjacent residential use | screening wall around dumpsters proposed |
| Private streets and shared driveways | 1 tree per 30lf; buffer between adjacent parcel and shared driveway/private street | Not applicable |

*Checks for street tree escrow are to be made payable to City of Ann Arbor and mailed to Systems Planning Unit, 301 E. Huron Street, PO Box 8647, Ann Arbor, Michigan 48107-8647. Attn: Tiffany Giacobazzi. Include the project name and number on the check.

PLANT SCHEDULE

| Total | Street Tree (-S) | ROW Screening (-R) | Symbol | Botanical Name | Common Name | Size | Spacing | Root | Remarks |
|------------------------|------------------|--------------------|--------|--|--------------------------------|-----------|----------|------|-----------|
| Deciduous Trees | | | | | | | | | |
| 9 | 9 | | Cca | <i>Cercis canadensis 'Ace of Hearts'</i> | Ace of Hearts Redbud | 2.5" cal. | 20' o.c. | B&B | tree form |
| 3 | 3 | | CC | <i>Cotinus coggygria</i> | European Smoketree | 2.5" cal. | 15' o.c. | B&B | |
| 3 | 3 | | OV | <i>Ostrya virginiana</i> | Hop Hornbeam | 2.5" cal | 20' o.c. | B&B | |
| 4 | 4 | | PS | <i>Prunus sargentii</i> | Sargent Cherry | 2.5" cal. | 20' o.c. | B&B | tree form |
| 7 | 7 | | GB | <i>Ginkgo biloba 'Princeton Sentry'</i> | Princeton Sentry Ginkgo | 2.5" cal. | per plan | B&B | male only |
| 2 | 2 | | QI | <i>Quercus imbricaria</i> | Shingle Oak | 2.5" cal. | 25' o.c. | B&B | |
| 10 | 10 | | SR | <i>Syringa reticulata 'Ivory Silk'</i> | Japanese Tree Lilac | 2.5" cal. | 20' o.c. | B&B | |
| 5 | 0 | 5 | TO | <i>Thuja occidentalis 'Smaragd'</i> | Emerald Green Arborvitae | 4'-5" ht. | 6' ht | B&B | |
| 43 | 38 | 5 | Total | | | | | | |
| Shrubs | | | | | | | | | |
| 5 | | 5 | AM | <i>Aronia melanocarpa</i> | Black Chokeberry | #5 Cont. | 24" ht | | |
| 5 | | 5 | TT | <i>Taxus 'Tautonii'</i> | Taunton Yew | #5 Cont. | 24" ht | | |
| 7 | | 7 | VD | <i>Viburnum dentatum 'Christom'</i> | Blue Muffin Arrowwood Viburnum | #5 Cont. | 24" ht | | |
| 17 | 0 | 17 | Total | | | | | | |

The underground utilities shown have been located from field survey information and existing records. The surveyor makes no guarantees that the underground utilities shown comprise all such utilities in the area, either in-service or abandoned. The surveyor further does not warrant that the underground utilities shown are in the exact location indicated. Although the surveyor does certify that they are located as accurately as possible from the information available.

20213
 JOB No. 20213
 DATE: 7/9/2021
 SHEET 24 OF 25
 REV. DATE: 06-07-21
 CADD: JBB
 ENG: JAM
 PM: RCW
 TECH: 20213P.dwg
 CITY SUBMITTAL 2

RACQUET CLUB OF ANN ARBOR
 PUMP HOUSE & SITE RENOVATION
 SITE PLAN ADMINISTRATIVE AMENDMENT
 OVERALL LANDSCAPE PLAN

CLIENT
 RACQUET CLUB OF ANN ARBOR
 3010 HICKORY LANE
 ANN ARBOR, MI 48104
 BRENT SCHOMAKER
 734-216-0579

MIDWESTERN CONSULTING
 385 Plaza Drive Ann Arbor, Michigan 48108
 (734) 995-0200 • www.midwesternconsulting.com
 Land Development • Land Survey • Institutional • Municipal
 Wireless Communications • Transportation • Landfill Services

MA:\civil\134_Proj\2021\3\Detail\ed Engineer\ing\2021\3\04.dwg, 7/9/2021 2:08 PM, Jeremy A. Mattioli, L2.0 LANDSCAPE NOTES AND DETAILS, MCLLC PDF, p63
Copyright © 2021, Midwestern Consulting L.L.C. All rights reserved. No part of this drawing may be used or reproduced in any form or by any means, or stored in a database or retrieval system, without prior permission of Midwestern Consulting L.L.C.


LANDSCAPE NOTES

- 1. For any plant quantity discrepancies between the plan view and the plant schedules, the plant schedule shall take precedence.
- 2. Plant materials shall be selected and installed in accordance with standards established by the City of Ann Arbor.
- 3. Water outlets shall be provided within 150 feet of all required plantings except for street tree plantings.
- 4. All diseased, damaged or dead material shown on the site plan as proposed plantings shall be replaced by the end of the following growing season.
- 5. Restore disturbed areas with a minimum of four (4) inches of topsoil and then seed/fertilize/mulch.
- 6. All disturbed areas not to be mulch planting beds identified on the Landscape Plan shall be lawn areas. Fertilizer for the initial installation of lawns shall provide not less than one (1) pound of actual nitrogen per 1,000 sq ft of lawn area and shall contain not less than two percent (2%) potassium and four percent (4%) phosphoric acid.
Lawn (turfgrass) seed mix shall consist of:
 - 15% Rugby Kentucky Bluegrass
 - 10% Park Kentucky Bluegrass
 - 40% Ruby Creeping Red Fescue
 - 15% Pennine Perennial Ryegrass
 - 20% Scaldis Hard Fescue
 Seed shall be applied at a rate of five pounds (5 lbs) per 1000 sq ft. Mulch within 24 hours with two (2) tons of straw per acre, or 71 bales of excelsior mulch per acre. Anchor straw mulch with spray coating of adhesive material applied at the rate of 150 gals./acre.
- 7. After the first growing season, only fertilizers that contain NO phosphorus shall be used on the site.
- 8. All seeded areas with slopes less than 1:3 (one vertical foot for every 3 horizontal feet) shall be mulched with straw mulch at the rate of two (2) bales per 1,000 square feet. All seeded areas with slopes greater than 1:3 shall be seeded and biodegradable erosion control blanket North American Green SC150, or equivalent, shall be applied with biodegradable stakes.
- 9. Deciduous plants shall be planted between March 1 and May 15 and from October 1 until the prepared soil becomes frozen. Evergreen plants shall be planted between March 1 and June 1 and from August 15 to September 15.
- 10. All planting beds are to receive four (4) inches of shredded hardwood bark mulch.
- 11. All trees to be located a minimum of 10 feet from public utilities.
- 12. All single trunk, deciduous trees shall have a straight and a symmetrical crown with a central leader. One sided trees or those with thin or open crowns shall not be accepted.
- 13. All evergreen trees shall be branched fully to the ground, symmetrical in shape and have not been sheared in the last three (3) growing seasons.
- 14. All compacted subgrade soils in proposed landscape areas shall be tilled to a minimum 12-inch depth prior to placement of topsoil, geotextile fabric, or other planting media as specified.
- 15. Proposed trees will be planted a minimum of 15 feet apart.
- 16. Planting Soil: Existing, in place or stockpiled topsoil. Supplement with imported topsoil as needed. Verify suitability of existing surface soil to produce viable planting soil. Remove stones, roots, plants, sod, clods, clay lumps, pockets of coarse sand, concrete slurry, concrete layers or chunks, cement, plaster, building debris, and other extraneous materials harmful to plant growth. Mix surface soil with the following soil amendments to produce planting soil:
 a. Ratio of Loose Compost to Topsoil by Volume: 1:4.
 b. Weight of Lime per 1000 Sq. Ft.: Amend with lime only on recommendation of soil test to adjust soil pH.
 c. Weight of Sulfur or Aluminum Sulfate per 1,000 Sq. Ft.: Amend with sulfur or aluminum sulfate only on recommendation of soil test to adjust soil pH.
 d. Volume of Sand: Amend with sand only on recommendation of Landscape Architect to adjust soil texture.
 e. Weight of Slow-Release Fertilizer per 1,000 Sq. Ft.: Amend with fertilizer only on recommendation of soil test to adjust soil fertility.
- 17. Snow cannot be pushed onto interior islands unless they are designated on the plan for snow storage. Bio-retention islands can be used for snow storage.

Maintenance:


- 1. Maintain plantings by pruning, cultivating, watering, weeding, fertilizing, mulching, restoring planting saucers, adjusting and repairing tree-stabilization devices, resetting to proper grades or vertical position, and performing other operations as required to establish healthy, viable plantings. Spray or treat as required to keep trees and shrubs free of insects and disease.
- 2. Fill in as necessary soil subsidence that may occur because of settling or other processes. Replace mulch materials damaged or lost in areas of subsidence.
- 3. Apply treatments as required to keep plant materials, planted areas, and soils free of pests and pathogens or disease. Use integrated pest management practices whenever possible to minimize the use of pesticides and reduce hazards. Treatments include physical controls such as hosing off foliage, mechanical controls such as traps, and biological control agents.
- 4. Contractor shall warrant all plant material and trees to remain alive and be in healthy, vigorous and like new condition for the specified period from installation to Substantial Completion. The entire Landscaping Project, including but not limited to: plants (perennials), trees, shrubs, mulches, shrubs, etc are to be under Warranty for One Year after Substantial Completion date of the Project. At the end of the specified One Year Warranty period the Owner's Representative will inspect plant material for compliance. Contractor shall replace, in accordance with the drawings and specifications, all plants, trees, shrubs, etc or as determined by the Owner's Representative, are in an unhealthy or unsightly condition. Warranty shall not include damage or loss of plants, trees, and shrubs caused by fires, floods, freezing rains, lightning storms, or winds over 75 miles per hour, acts of vandalism or negligence on the part of the owner, or any other incident beyond landscape contractor's control.
- 5. Long-term maintenance of the bio-retention island shall be performed by the Owner. Maintenance shall include seasonal trimming and removal of dead foliage, removal of weeds, and removal or mulching of leaves and stems. Spot treatment/removal of invasive weeds may be necessary if localized areas become dominated by invasive weeds. Bio-retention island shall be inspected by owner following any storm event exceeding 1". Trash and debris shall be removed as needed. Shredded hardwood mulch must be re-spread when erosion is evident and be replenished annually. Once every 2 to 3 years, the entire bio-retention/rain garden area may require mulch replacement.
- 6. Turf installations shall meet the following criteria as determined by Owner:
 a. Satisfactory Seeded Turf: At end of maintenance period, a healthy, uniform, close stand of grass has been established, free of weeds and surface irregularities, with coverage exceeding 90 percent over any 10 sq. ft. and bare spots not exceeding 5 by 5 inches.
 b. Satisfactory Sodded Turf: At end of maintenance period, a healthy, well-rooted, even-colored, viable turf has been established, free of weeds, open joints, bare areas, and surface irregularities.
 c. Use specified materials to reestablish turf that does not comply with requirements and continue maintenance until turf is satisfactory.
- 7. All plant species deviations from the approved site plan must be approved by the City of Ann Arbor in writing, prior to installation.

NOTE: REMOVE STAKING/GUYING MATERIAL AFTER ONE YEAR.



EVERGREEN TREE PLANTING DETAIL
NOT TO SCALE


DO NOT TRIM EVERGREENS
SHRUB SHALL BEAR SAME RELATION TO FINISH GRADE AS IN NURSERY
DO NOT PLANT SHRUBS TO WITHIN 42" OF TREE TRUNKS IN SHRUB BEDS




SHRUB PLANTING DETAIL
NOT TO SCALE

NOTE: PRUNE 20% OF BRANCHES AND FOLIAGE RETAINING NORMAL PLANT SHAPE

DO NOT TRIM EVERGREENS
SHRUB SHALL BEAR SAME RELATION TO FINISH GRADE AS IN NURSERY



EVERGREEN SHRUB PLANTING DETAIL
NOT TO SCALE



DO NOT STAKE UNLESS IN HEAVY CLAY SOIL, WINDY CONDITIONS, 3" OR GREATER DIAMETER TREE TRUNK OR LARGE CROWN. IF STAKING IS NEEDED DUE TO THESE CONDITIONS:


- STAKE WITH 2 x 2 HARDWOOD STAKES, OR APPROVED EQUAL, DRIVEN 6"-8" OUTSIDE OF ROOTBALL.
- LOOSELY STAKE TREE TRUNK TO ALLOW FOR TRUNK FLEXING.
- STAKE TREES JUST BELOW FIRST BRANCH WITH 2"-3" WIDE BELT-LIKE, NYLON OR PLASTIC STRAPS (2 PER TREE ON OPPOSITE SIDES OF TREE, CONNECT FROM TREE TO STAKE HORIZONTALLY. DO NOT USE ROPE OR WIRE THROUGH A HOSE.)
- REMOVE ALL STAKING MATERIALS AFTER 1 YEAR.

| REVISIONS | | | | REV. NO. | DR. BY | CH. BY | DATE |
|-----------|--|--|--|----------|--------|--------|------|
| | | | | | | | |

**PUBLIC SERVICES DEPARTMENT
CITY OF ANN ARBOR**


TREE PLANTING DETAIL

| | | | | |
|--------|------|--------|---------|--------------|
| DR. BY | ARG | CH. BY | CSS | DRAWING NO. |
| SCALE | NONE | DATE | 7-23-10 | SD-L-3 |
| INCH | | | | SHEET NO. OF |



ANNUAL AND PERENNIAL PLANTING
NOT TO SCALE

NOTE: PRUNE 20% OF BRANCHES AND FOLIAGE RETAINING NORMAL PLANT SHAPE
DO NOT TRIM EVERGREENS
SHRUB SHALL BEAR SAME RELATION TO FINISH GRADE AS IN NURSERY
PLANT SHRUBS TO WITHIN 42" OF TREE TRUNKS IN SHRUB BEDS



ARBORVITAE PLANTING DETAIL
NOT TO SCALE

The underground utilities shown have been located from field survey information and existing records. The surveyor makes no guarantees that the underground utilities shown comprise all such utilities in the area, either in-service or abandoned. The surveyor further does not warrant that the underground utilities shown are in the exact location indicated. Although the surveyor does certify that they are located as accurately as possible from the information available.

MIDWESTERN CONSULTING
385 Plaza Drive Ann Arbor, Michigan 48106
(734) 995-0200 • www.midwesternconsulting.com
Land Development • Land Survey • Institutional • Municipal
Wireless Communications • Transportation • Landfill Services

RACQUET CLUB OF ANN ARBOR
3010 HICKORY LANE
ANN ARBOR, MI 48104
BRENT SCHOMAKER
734-216-0579

PUMP HOUSE & SITE RENOVATION
SITE PLAN ADMINISTRATIVE AMENDMENT
LANDSCAPE NOTES AND DETAILS

L2.0

| | | | |
|------------|----------|---------|--------------|
| DATE: | 7/9/2021 | ISSUED: | 06-07-21 |
| SHEET: | 25 OF 25 | CADD: | JB |
| REV. DATE: | 06-07-21 | ENG.: | JAM |
| | | PM: | RCW |
| | | TECH: | 20213124.dwg |

JOB No. **20213**